

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03220210	Call Order: 002	Proposal: E3V56	District:03
Counties:	ESCAMBIA			
Road Name:	INTERSECTION IMPROVEMENT			
Limits:	48050000			
Project(s):	44986515201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.258 Miles	Contract Days:	90	
Total Bridge Length:	0.000 Miles	Letting Date:	02/10/22	
Total Proposal Length:	0.258 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Day Acquisition	
Proposal Budget Estimate:	\$849,892.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of SR 292 Sorrento Rd at Nighthawk Lane Intersection Improvement in Escambia County from MP 10.004 to MP 10.262. The project will include widening to add a new eastbound left turn lane as well as milling and resurfacing, driveways, shoulder grading, side drain pipe, and signing and pavement markings.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 002 Proposal: E3V56

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44986515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44986515201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,260.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,255.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	929.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	208.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.730
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	1.460
	0104- 10- 3	SEDIMENT BARRIER	LF	2,646.000
	0110- 1- 1	CLEARING & GRUBBING (44986515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	346.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	2.000
	0120- 1-	REGULAR EXCAVATION	CY	697.100
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	912.900
	0160- 4-	TYPE B STABILIZATION	SY	3,942.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,569.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,717.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	3,520.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	178.100
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	467.900
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	24.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	69.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	14.000
	0430-530-210	STRAIGHT CONCRETE ENDWALLS, 30", DOUBLE, 15 DEGREES, ROUND	EA	1.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0430-984-638	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 36" SD	EA	2.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	234.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,204.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.312
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.625
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44986515201)	LS	1.000
Section 0002 Signing				
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	132.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44986515201)	LS	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	204.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.554
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.832