

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03220113 Call Order: 003 Proposal: E3V60-R0 District:03
Counties: JACKSON, WASHINGTON
Road Name: MARIANNA MAINTENANCE - DRAINAGE REPAIR AND REPLACEMENT
Limits: Midpoint
Project(s): 42212227220(*) Federal Aid No: N/A
Total Roadway Length: 0.000 Miles Contract Days: THRU 12/31/22
Total Bridge Length: 0.000 Miles Letting Date: 01/13/22
Total Proposal Length: 0.000 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 15 Days
Proposal Budget Estimate: \$100,000.00

Please read the full advertisement

Description:

The Improvements under this Work Document-Driven Contract consists of repair and/or replacement of drainage elements on various roads in Jackson and Washington Counties. This work includes dewatering, desilting, cleaning, and repairing leaks in pipes and manholes, installing pipe liner, repairing, or replacing inlets and mitered end sections. Maintenance of Traffic and Mobilization are incidental to the pay items listed.

This contract has a budgetary ceiling of \$100,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

A Proposal Guaranty will not be required on indefinite quantity contracts, such as work document driven contracts, with an advertised budget amount of \$150,000 or less regardless of the bid amount.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 003 Proposal: E3V60-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MANUAL) (TN)				
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	30.000
	0104- 10- 3	SEDIMENT BARRIER	LF	125.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2.000
	0425- 3- 50	JUNCTION BOX, DRAINAGE, REPAIR	EA	11.000
	0425- 15- 41	INLET TOP, REPAIR, CURB INLET	EA	5.000
	0425- 15- 42	INLET TOP, REPAIR, DITCH BOTTOM INLET	EA	5.000
	0425- 15- 51	INLET TOP, REPLACE, CURB INLET	EA	4.000
	0425- 15- 52	INLET TOP, REPLACE, DITCH BOTTOM INLET	EA	1.000
	0430- 96-	DRAINAGE PIPE REPAIR- CONCRETE COLLAR AT JOINT	EA	4.000
	0430-174-112	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 12"SD	LF	12.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	12.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	36.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	36.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	12.000
	0430-174-136	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	LF	12.000
	0430-982-123	MITERED END SECTION, OPTIONAL ROUND, 15" CD	EA	10.000
	0430-984-121	MITERED END SECTION, OPTIONAL ROUND, 12" SD	EA	2.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	10.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	10.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	2.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	2.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	15.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	10.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	5.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	4.000
	E431- 1- 21	PIPE LINER, CURED IN PLACE, 0-24"	LF	25.000
	E431- 1- 22	PIPE LINER, CURED IN PLACE, 25-36"	LF	25.000
	E431- 1- 23	PIPE LINER, CURED IN PLACE, 37-48"	LF	15.000