

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03220113 Call Order: 006 Proposal: E3V63 District:03

Counties: HOLMES

Road Name: PONCE DE LEON MAINTENANCE - S.R. 79 SHOULDER REWORK

Limits: 52002000

Project(s): 42214327256(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	01/13/22
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$200,000.00

Please read the full advertisement

Description:

The Improvements under this Site-Specific Contract consist of reshaping ditches and reworking shoulders along State Road 79 in Holmes County from CR 173/CR177A (Mile Post 4.070) to the Alabama State Line (Mile Post 17.674). These ditches are non-typical and should be re-graded to +/- 3 inches of the original flow line to create a free and unobstructed flow of drainage water. For the purposes of this contract, the original flow line is considered to be the linear projection along the ditch bottom between the invert elevations of immediately adjacent drainage structures. Spoil material removed from ditches and shoulders shall be relocated to the FDOT storage pit in Caryville. Fertilization will be required on all locations where shoulder rework activities are performed. Mobilization and Maintenance of Traffic shall be incidental to the bid items.

Call Order: 006 Proposal: E3V63

ALT	Item	Description	Unit	Quantity
Section 0001 SODDING (SY)				
	0104- 10- 3	SEDIMENT BARRIER	LF	1,000.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	40.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	13,000.000
	E570- 2-	SEED & MULCH	SY	13,000.000
	E570- 5-	FERTILIZER	TN	5.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	35.000
	E573- 1-	HYDRO-SEEDING - APPLICATION OF SLURRY INCLUDING WOOD FIBER, SEED, FERTILIZER, TACKIFIER & DYE	SY	4,840.000
	E575- 1-	SODDING	SY	17,000.000
	E577- 70-	SHOULDER REWORK	SY	17,000.000
	E577- 71-	BLADING PAVED SHOULDER, UP TO 24" BEYOND PAVEMENT	LF	113,000.000