Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting:	03220113	Call Order: 008	Proposal	E3V65-R0	District:03			
Counties:	HOLMES, WALTON, WASHINGTON							
Road Name: Limits:	PONCE DE LEON MAINT DRAINAGE CLEANING AND MAINTENANCE 52002000							
Project(s): 42	214327287(*)	Federal Aid	d No: N/A					
Total Roadway Length:		0.432 Miles		Contract Days:	THRU 12/31/22			
Total Bridge Length:		0.000 Miles		Letting Date:	01/13/22			
Total Proposal Length:		0.432 Miles		Contract Execution Days:	10			
				Special Start Date:	N/A			
				Aquis/Flexible Start Time:	15 Days			
Proposal Budget Estimate:		9	\$250,000.00)				
Please read the full advertisement								

Description:

The Improvements under this Work Document-Driven Contract consist of cleaning of drainage structures and drainage ditches along various State Roads throughout Holmes, Walton, and a portion of Washington Counties. Maintenance of Traffic and Mobilization are incidental to the bid items listed.

This contract has a budgetary ceiling of \$250,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Call Order: 008 Proposal: E3V65-R0								
ALT	Item	Description	Unit	Quantity				
Section	0001 REPAIRIN	G NON-PAVED SHLDRS (MANUAL) (SY)						
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	400.000				
	E120-10-2	CLEAN AND RESHAPE DITCH (HAUL)	LF	2,000.000				
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	200.000				
	E425-73-5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	200.000				
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	11,000.000				
	E430-94-2	DESILT PIPE, 25-36"	LF	7,000.000				
	E430-94-3	DESILT PIPE, 37-48"	LF	2,400.000				
	E430-94-4	DESILT PIPE, 49-60"	LF	1,400.000				
	E430-94-5	DESILT PIPE, 61" OR GREATER	LF	400.000				
	E430-949- 13	DESILTING PIPE (UNDERDRAIN) (4")	LF	2,000.000				
	E430-949- 16	DESILTING PIPE (UNDERDRAIN) (6")	LF	2,000.000				
	E570- 2-	SEED & MULCH	SY	400.000				
	E577- 71-	BLADING PAVED SHOULDER, UP TO 24" BEYOND PAVEMENT	LF	1,000.000				