

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03220113 Call Order: 009 Proposal: E3V66-R0 District:03

Counties: HOLMES, WALTON, WASHINGTON

Road Name: ROUTINE MAINTENANCE - GUARDRAIL - ASPHALT REMOVE AND REPLACE

Limits: 52002000

Project(s): 42214327295(*) Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: 12/31/22

Total Bridge Length: 0.000 Miles Letting Date: 01/13/22

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 15 Days

Proposal Budget Estimate: \$200,000.00

Please read the full advertisement

Description:

The Improvements under this Work Document Driven Contract consist of removing and replacing existing guardrail asphalt pads and asphalt flumes along various roadways in Holmes, Walton, and a portion of Washington Counties. Shoulder rework and sodding may be necessary at each location. Fertilization will be required on all locations where shoulder rework activities are performed. Removal and replacement of guardrail may be necessary to accomplish work. All guardrail to be replaced at end of each workday. Mobilization, Maintenance of Traffic, and removal & replacement of guardrail shall be incidental to the pay items listed.

This Contract has a budgetary ceiling of \$200,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Call Order: 009 Proposal: E3V66-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MANUAL) (TN)				
	0104- 10- 3	SEDIMENT BARRIER	LF	1,000.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	200.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	500.000
	E110- 70-	REMOVAL OF FLEXIBLE PAVEMENT	SY	3,000.000
	E570- 5-	FERTILIZER	TN	2.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	10.000
	E575- 1-	SODDING	SY	2,400.000
	E577- 70-	SHOULDER REWORK	SY	2,400.000