

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting: 03220714      Call Order: 001      Proposal: E3U83      District:03  
Counties: OKALOOSA  
Road Name: - BRIDGE-REPAIR/REHABILITATION  
Limits: 57030000  
Project(s): 41768355201(\*)      Federal Aid No: N/A  
Total Roadway Length: 1.226 Miles      Contract Days: 200  
Total Bridge Length: 1.217 Miles      Letting Date: 07/14/22  
Total Proposal Length: 2.443 Miles      Contract Execution Days: 10  
Special Start Date: N/A  
Aquis/Flexible Start Time: 15 day Acquis.  
Proposal Budget Estimate: \$2,675,758.00

Please read the full advertisement

Description:

The improvements under this District Contract consist of cleaning and sealing bridge deck surface, spall repairs, & joint replacement on SR 30 (US 98) over East Pass Bridge Nos. 570054 & 570082 in Okaloosa County.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 001 Proposal: E3U83**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (41768355201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (41768355201)	LS	1.000
	0400- 32-	CONCRETE FOR JOINT REPAIR	CY	8.400
	0400- 45- 3	CLEANING AND COATING CONCRETE SURFACES, APPLIED FINISH COATING	SF	40,651.000
	0401- 70- 2	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- STYRENE BUTADIENE	CF	32.900
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	4.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	386.000
	0413-151-	METHACRYLATE MONOMER	GA	2,590.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	258,921.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	2,655.000
	0458- 1- 22	BRIDGE DECK EXPANSION JOINT, REHABILITATION, STRIP SEAL	LF	94.000
	0458- 1-100	BRIDGE DECK EXPANSION JOINT, POURED JOINT WITHOUT BACKER ROD, PROJECT 417683-5-52-01	LF	1,736.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	58.500
	0460- 1- 15	STRUCTURAL STEEL - REHABILITATION, MISCELLANEOUS	LB	40,793.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (41768355201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (41768355201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,420.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	19,290.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	296.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	235.000
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	2.434
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	2.434
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	2.434
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	2.434
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (41768355201)	LS	1.000
<b>Section 0003 Signing</b>				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	160.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.217
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	1.217
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.217
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	1.217