Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03220714 Call Order: 002 Proposal: E3V26 District:03

Counties: BAY

Road Name: - BRIDGE-REPAIR/REHABILITATION

Limits: 46070000

Project(s): 42358635201(*) Federal Aid No: N/A

Total Roadway Length:	0.043 Miles	Contract Days:	75
Total Bridge Length:	0.043 Miles	Letting Date:	07/14/22
Total Proposal Length:	0.086 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Day Acquis.

Proposal Budget Estimate: $415,656.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of restore spalled areas in the top of deck and concrete diaphragms, seal top of deck, clean and paint superstructure steel and bearing assemblies, clean and epoxy coat pile jacket surfaces, and other incidental construction for SR 388 over Crooked Creek, Bridge No. 460051 in Bay County.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 002 Proposal: E3V26

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	936.000
	0400-150-	CLEANING AND SEALING EXISTING CONCRETE SURFACE	SF	1,515.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	33.000
	0413-151-	METHACRYLATE MONOMER	GA	77.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	7,667.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	140.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (42358635201)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (42358635201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42358635201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,275.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,512.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	178.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	150.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42358635201)	LS	1.000
Section 0003 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	7.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.086
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.043