

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03220908	Call Order: 002	Proposal: E3W01	District:03
Counties:	SANTA ROSA			
Road Name:	RESURFACING			
Limits:	58010000			
Project(s):	44559115201(*)	Federal Aid No:	N/A	
Project(s):	44559115202	Federal Aid No:	N/A	
Total Roadway Length:	10.176 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	09/08/22	
Total Proposal Length:	10.176 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days Standard Acq	

Proposal Budget Estimate: \$9,365,835.00

Please read the full advertisement

Description:

The Improvements under this District Contract FPID 445591-1-52-01 consist of milling and resurfacing SR 10 (US 90) From West of SR 281 (Avalon Boulevard) to East of SR 87 (Stewart Street). The milling and resurfacing segments include roadway widening, turn lanes, signalization improvements, sidewalk, minor drainage improvements and curb ramps. FPID 445591-1-52-02 includes utility adjustments to gas valve boxes, sewage force main valves boxes, watermain valves boxes and sanitary sewer man-holes. All work to be done in Santa Rosa County.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 002 Proposal: E3W01

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44559115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44559115201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	128.300
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	384.000
	0102- 60-	WORK ZONE SIGN	ED	23,748.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	116,793.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	6,978.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	409.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,516.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	2,190.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,190.000
	0102-115-	TYPE III BARRICADE	ED	1,211.000
	0104- 10- 3	SEDIMENT BARRIER	LF	7,745.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	163.000
	0107- 1-	LITTER REMOVAL	AC	538.560
	0107- 2-	MOWING	AC	538.560
	0110- 1- 1	CLEARING & GRUBBING (44559115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,326.000

Call Order: 002 Proposal: E3W01

ALT	Item	Description	Unit	Quantity
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	2.000
	0120- 1-	REGULAR EXCAVATION	CY	1,116.500
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,180.600
	0160- 4-	TYPE B STABILIZATION	SY	1,012.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	388.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	393.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	1,623.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	161.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	4,142.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	57,813.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	71,127.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	6,274.400
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	11,471.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	6.500
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	7.000
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	1.000
	0425- 1-411	INLETS, CURB TYPE J-1, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	2.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	1.000
	0425- 1-563	INLETS, DITCH BOTTOM, TYPE F, J BOT, <10'	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	7.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	4.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	6.000
	0425- 6-	VALVE BOXES, ADJUST	EA	12.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	12.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	8.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	32.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	10.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	1.000
	0440- 1- 10	UNDERDRAIN, TYPE I	LF	250.000
	0440- 70-	UNDERDRAIN INSPECTION BOX	EA	2.000
	0440- 73- 1	UNDERDRAIN OUTLET PIPE, 4"	LF	36.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	818.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	56.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	7.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	173.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	679.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,521.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	82.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	80.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	3,363.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	2,370.000

Call Order: 002 Proposal: E3W01

ALT	Item	Description	Unit	Quantity
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	312.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,735.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	9,015.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	4,235.000
	0590- 70- 1	IRRIGATION SYSTEM REPAIRS (44559115201)	LS	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	9,358.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	26.448
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.824
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	13,708.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,670.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	8,618.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	4.017
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	32.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	520.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	12.570
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	364.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	2.398
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44559115201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	66.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	27.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	27.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	34.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	54.000
	0704- 1- 2	TUBULAR MARKER, DURABLE, 36" YELLOW POST	EA	89.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,679.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	830.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44559115201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	6,854.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,335.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,259.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.339
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	16.000

Call Order: 002 Proposal: E3W01

ALT	Item	Description	Unit	Quantity
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	260.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	182.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.199
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	100.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,981.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	29.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	29.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	8.795
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.627
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 1C-30 SKIP OR 3-9 LANE DROP	GM	4.743
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.168
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	627.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,499.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	7.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	30.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	8.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	3.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1.000
	0650- 1- 70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	5.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	4.000
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	3.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	7.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	6.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	60.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	30.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	2.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	5.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	7.000
	0682- 1-600	ITS CCTV CAMERA, REMOVE & DISPOSAL	EA	7.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	3.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000

Call Order: 002 Proposal: E3W01

ALT	Item	Description	Unit	Quantity
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000