

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

| | | | | |
|---------------------------|----------------|----------------------------|-----------------|-------------|
| Letting: | 03230810 | Call Order: 002 | Proposal: E3W55 | District:03 |
| Counties: | JEFFERSON | | | |
| Road Name: | REST AREA | | | |
| Limits: | 54001000 | | | |
| Project(s): | 22266925201(*) | Federal Aid No: N/A | | |
| Total Roadway Length: | 2.012 Miles | Contract Days: | 315 | |
| Total Bridge Length: | 0.000 Miles | Letting Date: | 08/10/23 | |
| Total Proposal Length: | 2.012 Miles | Contract Execution Days: | 10 | |
| | | Special Start Date: | N/A | |
| | | Aquis/Flexible Start Time: | 84 Days Other | |
| Proposal Budget Estimate: | \$5,901,405.00 | | | |

Please read the full advertisement

Description:

The Improvements under this District Contract consist of upgrading and expanding the SR 8 (I-10) Jefferson County Rest Areas wastewater treatment facility and spray field expansion at Mile Post 18.838 in Jefferson County. Proposed activities include updating equipment at the eastbound rest area and existing spray field, installing a force main along the north side of I-10 to connect to a new spray field expansion area; clearing, grubbing, and constructing a pond on the proposed spray field property; and stabilizing existing dirt roads that access the new spray field property with lime rock. The existing spray field at the EB rest area will remain in service and the newly proposed spray field will supplement.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT.

Call Order: 002 Proposal: E3W55

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|--|------|------------|
| Section 0001 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (22266925201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (22266925201) | LS | 1.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 6,580.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 3,150.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 630.000 |
| | 0104- 10- 3 | SEDIMENT BARRIER | LF | 5,950.000 |
| | 0104- 15- | SOIL TRACKING PREVENTION DEVICE | EA | 2.000 |
| | 0107- 1- | LITTER REMOVAL | AC | 147.290 |
| | 0107- 2- | MOWING | AC | 136.490 |
| | 0110- 1- 1 | CLEARING & GRUBBING (22266925201) | LS | 1.000 |
| | 0120- 1- | REGULAR EXCAVATION | CY | 815.000 |
| | 0120- 2- 2 | BORROW EXCAVATION, TRUCK MEASURE | CY | 21,659.000 |
| | 0285-706- | OPTIONAL BASE, BASE GROUP 06 | SY | 20,385.000 |
| | 0425- 1-521 | INLETS, DT BOT, TYPE C,<10' | EA | 6.000 |
| | 0430-174-118 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD | LF | 56.000 |
| | 0430-175-118 | PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD | LF | 4.000 |
| | 0430-175-130 | PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD | LF | 4.000 |
| | 0430-984-125 | MITERED END SECTION, OPTIONAL ROUND, 18" SD | EA | 4.000 |
| | 0444- 75- 2 | DEEP WELL- MONITOR WELL | EA | 2.000 |
| | 0531- 1-100 | IMPERMEABLE POND LINER | SY | 2,724.000 |
| | 0550- 10-110 | FENCING, TYPE A, 0.0-5.0', STANDARD | LF | 3,721.000 |

Call Order: 002 Proposal: E3W55

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|---|------|------------|
| | 0550- 10-118 | FENCING, TYPE A, 0.0-5.0', TYPE A STANDARD, RESET EXISTING | LF | 84.000 |
| | 0550- 60-125 | FENCE GATE, TYPE A, DOUBLE, 20.1-24.0' OPENING | EA | 5.000 |
| | 0570- 1- 1 | PERFORMANCE TURF | SY | 8,942.000 |
| | 0570- 1- 2 | PERFORMANCE TURF, SOD | SY | 703.000 |
| | 0570- 1-126 | PERFORMANCE TURF, SEEDING- COASTAL BERMUDA | SY | 76,338.000 |
| | 0570- 1-127 | PERFORMANCE TURF, SODDING- COASTAL BERMUDA | SY | 6,025.000 |
| | 0590- 70- | IRRIGATION SYSTEM (22266925201) | LS | 1.000 |
| | 0590- 70- 1 | IRRIGATION SYSTEM REPAIRS (22266925201) | LS | 1.000 |
| | 0639- 1-122 | ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR | AS | 2.000 |
| | 0639- 3- 11 | ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT | EA | 2.000 |
| | 0639- 5- 31 | EMERGENCY GENERATOR-PERMANENT 51-75 KW | EA | 1.000 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (22266925201) | LS | 1.000 |
| | 1000-100- 6 | WASTEWATER TREATMENT PLANT UPGRADE | LS | 1.000 |
| | 1050- 31-108 | UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, CASING/CONDUIT, 8" | LF | 638.000 |
| | 1050- 31-204 | UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 4" | LF | 6,377.000 |
| | 1050- 31-208 | UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 8" | LF | 54.000 |
| | 1050- 51-204 | UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 4" | LF | 174.000 |
| | 1080- 26-102 | UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 2" | EA | 5.000 |
| | 1501- 1- | LIFT STATION, SANITARY SEWER | EA | 2.000 |
| Section 0002 Signing | | | | |
| | 0700- 1- 11 | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF | AS | 46.000 |