Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03230810 Call Order: 004 Proposal: E3W98 District:03

Counties: LEON

Road Name: BRIDGE-REPAIR/REHABILITATION

Limits: 55070000

Project(s): 45055015201(*) Federal Aid No: N/A

Total Roadway Length:	0.021 Miles	Contract Days:	60
Total Bridge Length:	0.020 Miles	Letting Date:	08/10/23
Total Proposal Length:	0.041 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days Standard Acq

Proposal Budget Estimate: $124,156.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of SR 20 Crooked Rd Blountstown Hwy over Gum Creek Bridge No. 550163 installation of scour countermeasures and other incidental work, such as clearing and grubbing in Leon County, Florida (55070).

Call Order: 004 Proposal: E3W98

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	0.600
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	122.700
	0530- 74-	BEDDING STONE	TN	18.200
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (45055015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45055015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	456.000
	0102- 61-	BUSINESS SIGN	EA	8.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,458.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	52.000
	0102-115-	TYPE III BARRICADE	ED	84.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	189.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	120.000
	0110- 1- 1	CLEARING & GRUBBING (45055015201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	48.900
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45055015201)	LS	1.000