

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03230810 Call Order: 005 Proposal: E3X13 District:03

Counties: HOLMES, WALTON, WASHINGTON

Road Name: PONCE DE LEON MAINTENANCE - DITCH PAVEMENT AND RUBBLE

Limits: Midpoint

Project(s): 42214337207(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days: Thru	6/30/24
Total Bridge Length:	0.000 Miles	Letting Date:	08/10/23
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

Description:

The Improvements under this Work Document-Driven Contract consist of the removal and placement of concrete ditch pavement as well as installation of riprap rubble in Holmes, Walton, and a portion of Washington Counties. Some locations will require clearing and grubbing of 10 feet in width on each side of new concrete ditch pavement. Maintenance of Traffic and Mobilization will be incidental to the pay items provided. The budget estimate amount for this contract is \$500,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Call Order: 005 Proposal: E3X13

ALT	Item	Description	Unit	Quantity
Section 0001 SODDING (SY)				
	0104- 10- 3	SEDIMENT BARRIER	LF	500.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	100.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,000.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	40.000
	0120- 9- 1	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH UP TO 15'	LF	1,000.000
	0120- 10- 11	CLEAN AND RESHAPE DITCH, SPREAD, DITCH WIDTH UP TO 15'	LF	1,000.000
	0120- 10- 12	CLEAN AND RESHAPE DITCH, SPREAD, DITCH WIDTH 15-30'	LF	1,000.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	1,400.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	2,300.000
	E110- 2-	CLEARING & GRUBBING	AC	4.000
	E570- 2-	SEED & MULCH	SY	4,500.000
	E575- 1-	SODDING	SY	8,000.000