

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	03230608	Call Order: 001	Proposal: E3V81	District:03
Counties:	LEON			
Road Name:	RESURFACING			
Limits:	55110000			
Project(s):	44563415201(*)	Federal Aid No:	N/A	
Project(s):	44563415202	Federal Aid No:	N/A	
Project(s):	44563415203	Federal Aid No:	N/A	
Total Roadway Length:	14.046 Miles	Contract Days:	385	
Total Bridge Length:	0.000 Miles	Letting Date:	06/08/23	
Total Proposal Length:	14.046 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days Standard Acq	
Proposal Budget Estimate:	\$6,130,039.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of FPID 445634-1-52-01 for the milling and resurfacing of SR 155 MERIDIAN RD from SR 61 THOMASVILLE RD to CR 63A LAKESHORE DR, including sidewalk construction, ADA improvements, gravity wall repair/replacement, drainage inlet replacements, bridge railing retrofits for Bridge No. 550067, guardrail replacement, signing and pavement markings, mast arm replacements, and pedestrian signal improvements; FPID 445634-1-52-02 for manhole and valve box adjustments for City of Tallahassee Water and Sewer; and 445634-1-52-03 for manhole adjustments for Century Link in Leon County.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 001 Proposal: E3V81

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44563415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44563415201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44563415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	162.000
	0102- 60-	WORK ZONE SIGN	ED	33,052.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	13,634.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,816.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	15.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,197.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	2,695.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,310.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,441.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	84.000
	0107- 1-	LITTER REMOVAL	AC	68.400
	0107- 2-	MOWING	AC	68.400
	0110- 1- 1	CLEARING & GRUBBING (44563415201)	LS	1.000

Call Order: 001 Proposal: E3V81

ALT	Item	Description	Unit	Quantity
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.020
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,284.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	2.000
	0120- 1-	REGULAR EXCAVATION	CY	52.600
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	234.800
	0160- 4-	TYPE B STABILIZATION	SY	22.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	22.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	57,005.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	3,654.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	3,919.100
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	4,170.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	8.500
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	7.700
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	1,813.000
	0425- 1-315	INLETS, CURB TYPE P-1, PARTIAL	EA	3.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-481	INLETS, CURB, TYPE 8, <10'	EA	2.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	2.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	10.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	132.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	2.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	52.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,057.000
	0521- 5- 11	CONCRETE TRAFFIC RAILING- BRIDGE, RETROFIT-POST & BEAM RAILING	EA	2.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	519.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	860.000
	0527- 2-	DETECTABLE WARNINGS	SF	789.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	244.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-002, APPROACH TL-3	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	230.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0550- 10-218	FENCING, TYPE B, 0.0-5.0', RESET EXISTING	LF	43.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,609.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,523.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.985
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.089
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,429.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	46.000

Call Order: 001 Proposal: E3V81

ALT	Item	Description	Unit	Quantity
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	947.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.537
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.049
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	17.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	105.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.966
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,327.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.505
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.167
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44563415201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	19.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	11.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	11.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	8.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	12.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	12.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,523.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44563415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,359.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	46.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	947.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.049
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	17.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	105.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,327.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.167
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,113.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.985
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.089
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.537
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.966
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.503

Call Order: 001 Proposal: E3V81

ALT	Item	Description	Unit	Quantity
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	197.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.104
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.106
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.208
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.102
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,768.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,963.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	6.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	74.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	1.000
	0639- 1-410	ELECTRICAL POWER SERVICE, REL OVERHEAD	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	20.000
	0639- 2- 4	ELECTRICAL SERVICE WIRE, RELOCATE	LF	20.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	5.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	5.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	13.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	3.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	5.000
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	1.000
	0649- 21- 2	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 30'-30'	EA	1.000
	0649- 21- 7	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 50'-30'	EA	1.000
	0649- 21- 8	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 50'-40'	EA	1.000
	0649- 21- 11	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 60'-30'	EA	1.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	18.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	3.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	3.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	20.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	12.000

Call Order: 001 Proposal: E3V81

ALT	Item	Description	Unit	Quantity
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	5.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	6.000
	0654- 2- 12	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- AC, COMPLETE SIGN ASSEMBLY- BACK TO BACK	AS	2.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	17.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	34.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	15.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	22.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	3.000
	0670- 5-500	TRAFFIC CONTROLLER ASSEMBLY, RELOCATE CONTROLLER WITH CABINET	AS	1.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	3.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	1.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	7.000
Section 0004 Utilities				
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	78.000
	0425- 6-	VALVE BOXES, ADJUST	EA	57.000