

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

| | | | | |
|------------------------|----------------|----------------------------|----------------------|-------------|
| Letting: | 03230511 | Call Order: 003 | Proposal: E3W40 | District:03 |
| Counties: | OKALOOSA | | | |
| Road Name: | RESURFACING | | | |
| Limits: | 57110028 | | | |
| Project(s): | 44374425201(*) | Federal Aid No: | N/A | |
| Project(s): | 44374425202 | Federal Aid No: | N/A | |
| Total Roadway Length: | 7.332 Miles | Contract Days: | 240 | |
| Total Bridge Length: | 0.000 Miles | Letting Date: | 05/11/23 | |
| Total Proposal Length: | 7.332 Miles | Contract Execution Days: | 10 | |
| | | Special Start Date: | N/A | |
| | | Aquis/Flexible Start Time: | 15 Days Standard Acq | |

Proposal Budget Estimate: \$5,872,583.00

Please read the full advertisement

Description:

The Improvements under this District Contract include 443744-2-52-01 which consists of Milling and Resurfacing SR 393 Mary Esther Boulevard from SR 30 (US 98) to SR 189 Beal Pkwy in Okaloosa County. Additional work includes, but is not limited to, widening opposing left turn lanes at six intersections, sidewalk repairs, signal loop replacements and signing and pavement markings. For 443744-2-52-02, the improvements consist of utility manhole adjustments before, during and after paving operations.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT.

Call Order: 003 Proposal: E3W40

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|-------------|--|------|------------|
| Section 0001 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (44374425201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (44374425201) | LS | 1.000 |
| | 0102- 3- | COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE | CY | 30.000 |
| | 0102- 14- | TRAFFIC CONTROL OFFICER | HR | 399.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 20,960.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 31,320.000 |
| | 0102- 74- 8 | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | FD | 3,600.000 |
| | 0102- 76- | ARROW BOARD / ADVANCE WARNING ARROW PANEL | ED | 700.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 1,016.000 |
| | 0102-104- | TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION | ED | 2,400.000 |
| | 0102-107- 1 | TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION | ED | 2,400.000 |
| | 0104- 10- 3 | SEDIMENT BARRIER | LF | 1,096.000 |
| | 0104- 18- | INLET PROTECTION SYSTEM | EA | 65.000 |
| | 0107- 1- | LITTER REMOVAL | AC | 99.200 |
| | 0107- 2- | MOWING | AC | 30.960 |
| | 0110- 1- 1 | CLEARING & GRUBBING (44374425201) | LS | 1.000 |
| | 0110- 4- 10 | REMOVAL OF EXISTING CONCRETE | SY | 2,061.000 |
| | 0120- 1- | REGULAR EXCAVATION | CY | 691.400 |

Call Order: 003 Proposal: E3W40

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|--|------|------------|
| | 0120- 2- 2 | BORROW EXCAVATION, TRUCK MEASURE | CY | 106.700 |
| | 0160- 4- | TYPE B STABILIZATION | SY | 2,240.000 |
| | 0285-706- | OPTIONAL BASE, BASE GROUP 06 | SY | 2,053.000 |
| | 0327- 70- 5 | MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH | SY | 54,646.000 |
| | 0327- 70- 6 | MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH | SY | 29,170.000 |
| | 0334- 1- 53 | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22 | TN | 169.400 |
| | 0337- 7- 83 | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22 | TN | 8,449.400 |
| | 0425- 5- | MANHOLE, ADJUST | EA | 10.000 |
| | 0425- 5- 1 | MANHOLE, ADJUST, UTILITIES | EA | 2.000 |
| | 0520- 1- 7 | CONCRETE CURB & GUTTER, TYPE E | LF | 650.000 |
| | 0520- 1- 10 | CONCRETE CURB & GUTTER, TYPE F | LF | 699.000 |
| | 0520- 5- 11 | TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE | LF | 812.000 |
| | 0522- 1- | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK | SY | 1,181.000 |
| | 0522- 2- | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK | SY | 569.000 |
| | 0527- 2- | DETECTABLE WARNINGS | SF | 1,808.000 |
| | 0570- 1- 2 | PERFORMANCE TURF, SOD | SY | 1,479.000 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44374425201) | LS | 1.000 |
| Section 0002 Signing | | | | |
| | 0700- 1- 11 | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF | AS | 17.000 |
| | 0700- 1- 12 | SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF | AS | 3.000 |
| | 0700- 1- 60 | SINGLE POST SIGN, REMOVE | AS | 6.000 |
| | 0700- 2- 12 | MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF | AS | 2.000 |
| | 0700- 2- 14 | MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF | AS | 1.000 |
| | 0700- 2- 60 | MULTI- POST SIGN, REMOVE | AS | 3.000 |
| | 0700- 3-101 | SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF | EA | 62.000 |
| | 0700- 3-102 | SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF | EA | 1.000 |
| | 0700- 3-202 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF | EA | 1.000 |
| | 0700- 3-204 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF | EA | 1.000 |
| | 0700- 3-601 | SIGN PANEL, REMOVE, UP TO 12 SF | EA | 63.000 |
| | 0700- 3-602 | SIGN PANEL, REMOVE, 12-20 SF | EA | 1.000 |
| | 0700- 3-604 | SIGN PANEL, REMOVE, 31-50 SF | EA | 1.000 |
| | 0704- 1- 2 | TUBULAR MARKER, DURABLE, 36" YELLOW POST | EA | 39.000 |
| | 0706- 1- 3 | RAISED PAVEMENT MARKER, TYPE B | EA | 1,619.000 |
| | 0710- 11-290 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE | SF | 541.000 |
| | 0710- 90- | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44374425201) | LS | 1.000 |
| | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT | LF | 6,325.000 |
| | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS | LF | 911.000 |
| | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK | LF | 1,167.000 |
| | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" | GM | 0.066 |
| | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL | EA | 8.000 |
| | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW | EA | 124.000 |

Call Order: 003 Proposal: E3W40

| ALT | Item | Description | Unit | Quantity |
|-----------------------------------|--------------|--|------|-----------|
| | 0711- 11-180 | THERMOPLASTIC, STANDARD, WHITE, YIELD LINE | LF | 14.000 |
| | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON | LF | 113.000 |
| | 0711- 11-241 | THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6" | GM | 0.084 |
| | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK | LF | 3,707.000 |
| | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" | GM | 4.801 |
| | 0711- 16-102 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8" | GM | 0.591 |
| | 0711- 16-131 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 1C-30 SKIP OR 3-9 LANE DROP | GM | 2.767 |
| | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" | GM | 3.247 |
| Section 0003 Signalization | | | | |
| | 0611- 2- 1 | ITSFM LOCATION DOCUMENTATION- INTERSECTION | EA | 6.000 |
| | 0630- 2- 11 | CONDUIT, FURNISH & INSTALL, OPEN TRENCH | LF | 302.000 |
| | 0630- 2- 12 | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE | LF | 280.000 |
| | 0632- 7- 1 | SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL | PI | 6.000 |
| | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE | EA | 6.000 |
| | 0646- 1- 11 | ALUMINUM SIGNALS POLE, PEDESTAL | EA | 6.000 |
| | 0646- 1- 12 | ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST | EA | 15.000 |
| | 0646- 1- 60 | ALUMINUM SIGNALS POLE, REMOVE | EA | 2.000 |
| | 0650- 1- 14 | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY | AS | 47.000 |
| | 0650- 1- 18 | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY | AS | 28.000 |
| | 0650- 1- 60 | VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN | AS | 75.000 |
| | 0653- 1- 11 | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY | AS | 2.000 |
| | 0653- 1- 12 | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS | AS | 4.000 |
| | 0653- 1- 60 | PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN | AS | 5.000 |
| | 0660- 1-110 | LOOP DETECTOR INDUCTIVE, F&I, TYPE 10 | EA | 6.000 |
| | 0660- 2-101 | LOOP ASSEMBLY- F&I, TYPE A | AS | 70.000 |
| | 0660- 2-102 | LOOP ASSEMBLY, F&I, TYPE B | AS | 101.000 |
| | 0663- 1-121 | SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS | EA | 6.000 |
| | 0665- 1- 11 | PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD | EA | 23.000 |
| | 0665- 1- 60 | PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN | EA | 21.000 |
| | 0670- 5-111 | TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION | AS | 6.000 |
| | 0670- 5-600 | TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET | AS | 6.000 |
| | 0682- 1-133 | ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION | EA | 6.000 |
| | 0684- 1- 1 | MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL | EA | 6.000 |
| | 0685- 1- 14 | UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION WITH CABINET | EA | 6.000 |

Call Order: 003 Proposal: E3W40

| ALT | Item | Description | Unit | Quantity |
|-----|-------------|---|------|----------|
| | 0700- 3-101 | SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF | EA | 19.000 |
| | 0700- 3-202 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF | EA | 6.000 |
| | 0700- 3-601 | SIGN PANEL, REMOVE, UP TO 12 SF | EA | 19.000 |
| | 0700- 3-602 | SIGN PANEL, REMOVE, 12-20 SF | EA | 4.000 |