

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03231109 Call Order: 004 Proposal: E3W88 District:03
 Counties: WASHINGTON
 Road Name: SR10 (US90) FROM HOLMES CREEK BRIDGE TO SR277 - RESURFACING
 Limits: 61010000
 Project(s): 44575515201(*) Federal Aid No: N/A
 Total Roadway Length: 2.661 Miles Contract Days: 120
 Total Bridge Length: 0.000 Miles Letting Date: 11/09/23
 Total Proposal Length: 2.661 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Days Standard
 Proposal Budget Estimate: \$3,032,489.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of milling and resurfacing SR 10 (US 90) from east of Holmes Creek Bridge to SR 277 in Washington County under FPID 445755-1-52-01. Other improvements under this project include minor drainage improvements, signing and pavement marking, replacement of traffic monitoring sensors and loops, and expansion joint replacement at the end bents of existing Bridge No. 610002.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 004 Proposal: E3W88

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44575515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44575515201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,122.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	12,536.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	268.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	240.000
	0104- 10- 3	SEDIMENT BARRIER	LF	14,532.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	31.000
	0107- 1-	LITTER REMOVAL	AC	154.650
	0107- 2-	MOWING	AC	154.650
	0110- 1- 1	CLEARING & GRUBBING (44575515201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	24.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	587.400
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	35,787.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	152.000
	0327- 70- 16	MILLING EXISTING ASPHALT PAVEMENT, 1/2" AVG DEPTH	SY	16,450.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	3,251.700
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	4,320.400
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	58.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	6.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000

Call Order: 004 Proposal: E3W88

ALT	Item	Description	Unit	Quantity
	0430-990-	MITERED END SECT, REPLACE GRATE	EA	1.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	70.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	4.000
	0530- 74-	BEDDING STONE	TN	2.900
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	10,394.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	90.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	2.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	2.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	5.212
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.202
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.993
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44575515201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	7.468
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	8.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	8.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	3.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	16.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	619.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44575515201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	250.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	75.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.212
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.202
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.993
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.162
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.081