

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03231012	Call Order: 001	Proposal: E3V77	District:03
Counties:	OKALOOSA			
Road Name:	- BRIDGE-REPAIR/REHABILITATION			
Limits:	57518000			
Project(s):	40919375201(*)	Federal Aid No: N/A		
Total Roadway Length:	3.657 Miles	Contract Days:	335	
Total Bridge Length:	3.649 Miles	Letting Date:	10/12/23	
Total Proposal Length:	7.306 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Day Standard	
Proposal Budget Estimate:	\$4,551,146.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of restore spalled areas in the top of deck and outside faces of the box girder; clean and seal top of deck with methacrylate; concrete repair and galvanic cathodic protection system to Pier 104 columns and web wall; and other incidental construction for SR 293 over Choctawhatchee Bay, Bridge No. 570091 in Okaloosa County.

PREQUALIFICATION REQUIRED TO BID ON THIS PROJECT

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 001 Proposal: E3V77

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	148.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	7.000
	0400- 60- 3	CATHODIC PROTECTION - ELECTRICAL WORK, CONDUIT, WIRING, AND ACCESSORIES (40919375201)	LS	1.000
	0400- 60- 4	CATHODIC PROTECTION - ELECTRICAL WORK, EQUIPMENT & INSTRUMENTATION (40919375201)	LS	1.000
	0400-142- 9	CATHODIC PROTECTION SYSTEM, OTHER MATERIAL	SF	382.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	62.000
	0413-151-	METHACRYLATE MONOMER	GA	7,722.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	772,200.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	1,300.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (40919375201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (40919375201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	616.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	3,934.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	17,432.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	698.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	7.314
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	7.314
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (40919375201)	LS	1.000
Section 0003 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	7,724.000
	0918-712-100	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 6"	GM	7.314
	0918-712-110	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 6"	GM	7.314