

Florida Department of Transportation

Bid Solicitation Notice and Approximate Quantities

Letting:	03231012	Call Order: 011	Proposal: E3X47-R0	District:03
Counties:	SANTA ROSA			
Road Name:	BDI PROJECT - WDD CONCRETE REMOVAL AND REPLACEMENT			
Limits:	Midpoint			
Project(s):	42378147208(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	THRU 12/31/24	
Total Bridge Length:	0.000 Miles	Letting Date:	10/12/23	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 DAYS	
Proposal Budget Estimate:	\$150,000.00			

Please read the full advertisement

Description:

The improvements under this Work Document Driven Contract consist of the removal and replacement of sidewalk, driveways, curb and gutter, inlet tops, mitered end sections and other miscellaneous concrete items in Santa Rosa County on a call-out basis. Mobilization and Maintenance of Traffic are incidental to this contract.

The overall budget estimate for this contract will be \$150,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

A Proposal Guaranty will not be required on indefinite quantity contracts, such as work document driven contracts, with an advertised estimated budget amount of \$150,000 or less regardless of the bid amount.

BUSINESS DEVELOPMENT INITIATIVE Bidders must be a Small Business as defined by FDOT. Small business size standards can be found at: <https://www.fdot.gov/equalopportunity/>

For more information about bidding on BDI projects please see the training guide located at:

<http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required. Bidders must complete and submit the Small Business Affidavit Form No. 275-000-01 for approval prior to receipt of bid documents. The form may be accessed at:

<https://www.fdot.gov/equalopportunity/>

It is only necessary to submit the Small Business Affidavit form once per year. Send a completed and notarized affidavit as an attachment to fdot.bdi@dot.state.fl.us.

All Sublet work must be contracted to a small business or businesses as defined by the Department.

The subcontractor must also submit a notarized Small Business Affidavit Form provided by the Department prior to the start of work.

Call Order: 011 Proposal: E3X47-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MANUAL) (TN)				
	0104- 10- 3	SEDIMENT BARRIER	LF	50.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	3.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,000.000

Call Order: 011 Proposal: E3X47-R0

ALT	Item	Description	Unit	Quantity
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	200.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2.000
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	2.000
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	5.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	5.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	2.000
	0425- 82-	REPLACE GRATE	EA	3.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-518-110	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 15 DEGREES, ROUND	EA	2.000
	0430-518-120	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 30 DEGREES, ROUND	EA	2.000
	0430-518-130	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 45 DEGREES, ROUND	EA	5.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	5.000
	0430-524-200	STRAIGHT CONCRETE ENDWALLS, 24", DOUBLE, 0 DEGREES, ROUND	EA	2.000
	0430-530-100	STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 0 DEGREES, ROUND	EA	4.000
	0430-530-200	STRAIGHT CONCRETE ENDWALLS, 30", DOUBLE, 0 DEGREES, ROUND	EA	2.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	4.000
	0430-536-110	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 15 DEGREES, ROUND	EA	2.000
	0430-536-200	STRAIGHT CONCRETE ENDWALLS, 36", DOUBLE, 0 DEGREES, ROUND	EA	2.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	5.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	5.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	2.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	2.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	5.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	5.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	2.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	2.000
	0430-991-	MITERED END SECT, REPLACE SLAB- CONSTRUCTION USE	EA	200.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	500.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	50.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	250.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	200.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	850.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	850.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	1,000.000
	0527- 2-	DETECTABLE WARNINGS	SF	50.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	20.000
	E110- 70-	REMOVAL OF FLEXIBLE PAVEMENT	SY	200.000

Call Order: 011 Proposal: E3X47-R0

ALT	Item	Description	Unit	Quantity
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	2.000
	E425- 73- 3	FRAME AND GRATE (F&I)	EA	1.000
	E570- 2-	SEED & MULCH	SY	200.000
	E575- 1-	SODDING	SY	1,000.000