Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03230914 Call Order: 004 Proposal: E3X22 District:03

Counties: WALTON

Road Name: PONCE DE LEON MAINTENANCE - SHLDR REWORK AND DITCH CLEANING

Limits: Midpoint

Project(s): 42214337222(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	Thru 12/31/2024
Total Bridge Length:	0.000 Miles	Letting Date:	09/14/23
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 day

Proposal Budget Estimate: $300,000.00

Please read the full advertisement

Description:

The Improvements under this Work Document-Driven Contract consist of reshaping ditches and reworking shoulders along State Road 187 (US 331) in Walton County. These ditches are non-typical and should be re-graded to +/- 3 inches of the original flow line to create a free and unobstructed flow of drainage water. For the purposes of this contract, the original flow line is considered to be the linear projection along the ditch bottom between the invert elevations of immediately adjacent drainage structures. Spoil material removed from ditches and shoulders shall be relocated to FDOT storage pits in Argyle or Liberty. Mobilization and Maintenance of Traffic are incidental to the pay items listed.

Call Order: 004 Proposal: E3X22

ALT	Item	Description	Unit	Quantity
Section 0001 SODDING (SY)				
	0104- 10- 3	SEDIMENT BARRIER	LF	1,000.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	50.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	100.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	5,000.000
	E570- 5-	FERTILIZER	TN	5.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	600.000
	E573- 1-	HYDRO-SEEDING - APPLICATION OF SLURRY INCLUDING WOOD FIBER, SEED, FERTILIZER, TACKIFIER & DYE	SY	6,000.000
	E575- 1-	SODDING	SY	60,000.000
	E577- 70-	SHOULDER REWORK	SY	60,000.000