

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	03240411	Call Order: 006	Proposal: E3X81-R0	District:03
Counties:	SANTA ROSA			
Road Name:	MILTON OPS MAINTENANCE - OUTFALL DITCH MAINTENANCE			
Limits:	Midpoint			
Project(s):	42214237220(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	THRU 6/30/25	
Total Bridge Length:	0.000 Miles	Letting Date:	04/11/24	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 DAYS	
Proposal Budget Estimate:	\$375,000.00			

Please read the full advertisement

**Description:**

The Improvements under this Work Document-Driven Contract consist of cleaning vegetation and sediment from outfall ditches for the state roadway system within Santa Rosa County. This work includes removal of fallen trees, remove or mulch woody vegetation, remove or mulch overhanging limbs, remove sediment from concrete ditches and remove other debris located within the outfall ditch areas to maintain maximum drainage functionality. Sediment removal is limited to the concrete ditch bottoms where sediment exceeds 3 inches in depth. The ditch width specified in the pay item(s) shall include both the ditch bottom width and the previously maintained side slope. No grading is anticipated for this contract. Access to ditches may be limited, therefore, plan to perform all work within the limits of the ditch. If right of entry is required, the contractor is responsible for obtaining permission from adjacent landowners and restoring the property to original condition at no cost to the Department. Non-woody vegetation may be left on-site after cutting. Onsite disposal of mulched woody vegetation will be allowed provided there are no downstream drainage structures present, and mulch does not exceed one and one-half (1.5) inches in depth at any location. Maintenance of traffic and mobilization are incidental to the pay items listed.

**Call Order: 006 Proposal: E3X81-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ROADSIDE DITCHES-CLEAN AND RESHAPE (LF)</b>				
	E111- 1- 2	DITCH AND CANAL, CLEANING, 15'-30' WIDE	LF	46,234.000
	E111- 1- 3	DITCH AND CANAL, CLEANING, GREATER THAN 30' WIDE	LF	28,945.000