

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 03240411	Call Order: 007	Proposal: E3X82	District:03
Counties: WALTON			
Road Name: PONCE DE LEON MAINT - PLACE RUBBLE (BANK SHORE AND DITCH)			
Limits: Midpoint			
Project(s): 42214337219(*)	Federal Aid No: N/A		
Total Roadway Length: 0.000 Miles	Contract Days:	THRU 12/31/24	
Total Bridge Length: 0.000 Miles	Letting Date:	04/11/24	
Total Proposal Length: 0.000 Miles	Contract Execution Days:	10	
	Special Start Date:	N/A	
	Aquis/Flexible Start Time:	15 DAYS	
Proposal Budget Estimate:	\$200,000.00		

Please read the full advertisement

Description:

Improvements under this Work Document-Driven Contract consist of the placement of Bank and Shore Rubble as well as Ditch Lining Rubble along various roadways in Walton County. This rubble will be used to fill, re-contour and restore eroded slope and ditch bottoms. Periodic lane closures will be required. Removal and replacement of guardrail may be necessary to accomplish dumping and spreading of rubble. All guardrail to be replaced at the end of each workday. Mobilization, Maintenance of Traffic, and removal & replacement of guardrail shall be incidental to the pay items listed.

This Contract has a budgetary estimate of \$200,000.00.

**Call Order: 007 Proposal: E3X82**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)</b>				
	0104- 10- 3	SEDIMENT BARRIER	LF	100.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	100.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	20.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	5.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	800.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	20.000
	0530- 74-	BEDDING STONE	TN	20.000
	E575- 1-	SODDING	SY	150.000