

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	03241212	Call Order: 007	Proposal: E3Y46-R0	District:03
Counties:	GADSDEN, LEON			
Road Name:	MIDWAY OPS - WDD SHLDR BLADING AND GUARDRAIL PAD CLEANING			
Limits:	55320000			
Project(s):	42215127281(*)	Federal Aid No: N/A		
Total Roadway Length:	0.004 Miles	Contract Days:	THRU 12/31/25	
Total Bridge Length:	0.000 Miles	Letting Date:	12/12/24	
Total Proposal Length:	0.004 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$200,000.00			

Please read the full advertisement

Description:

The work under this Work Document-Driven Contract in Gadsden and Leon Counties consists of the removal of all vegetation, and debris on existing shoulders (paved and unpaved) and paved surfaces at guardrail installations. The work on shoulders consists of blading, restoration of positive grade and re-establishment of turf on any disturbed areas. Work Locations, descriptions and estimates will be provided in the Work Documents. Mobilization is incidental to the pay items listed. The summary of pay items for this project is listed in the Bid Price Proposal.

This contract has a budgetary estimate of \$200,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder, however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

**Call Order: 007 Proposal: E3Y46-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 TRAFFIC CONTROL DEVICES CONTROL (MH)</b>				
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	20.000
	0102- 60-	WORK ZONE SIGN	ED	530.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,200.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	53.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	53.000
	E102-100-	MOT MAINTENANCE SERVICES	HR	400.000
	E536- 15- 1	GUARDRAIL MAINTENANCE, VEGETATION AND DEBRIS REMOVAL	LF	15,000.000
	E573- 1-	HYDRO-SEEDING - APPLICATION OF SLURRY INCLUDING WOOD FIBER, SEED, FERTILIZER, TACKIFIER & DYE	SY	18,750.000
	E575- 1-	SODDING	SY	1,000.000
	E577- 70-	SHOULDER REWORK	SY	1,000.000
	E577- 70- 1	REWORKING SHOULDERS (SPOT REPAIRS)	SY	1,000.000
	E577- 70- 2	REWORKING UTILITY STRIPS	SY	1,000.000
	E577- 71-	BLADING PAVED SHOULDER, UP TO 24" BEYOND PAVEMENT	LF	60,000.000