

**Florida Department of Transportation  
 Bid Solicitation Notice and Approximate Quantities**

Letting: 03240208      Call Order: 001      Proposal: E3W87      District: 03

Counties: LIBERTY

Road Name: SR 65 FROM SR 20 TO GADSDEN COUNTY LINE - RESURFACING

Limits: 56040000

Project(s): 44573515201(\*)      Federal Aid No: N/A

Total Roadway Length: 6.145 Miles      Contract Days: 150

Total Bridge Length: 0.000 Miles      Letting Date: 02/08/24

Total Proposal Length: 6.145 Miles      Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 30 Days Flex.

Proposal Budget Estimate: \$4,145,713.00

Please read the full advertisement

Description:

The improvements under this District Contract FPID 445735-1-52-01 consist of milling and resurfacing SR 65 from North of SR 20 to Gadsden County Line in Liberty County. The milling and resurfacing segments include shoulder widening, side road improvements, and minor drainage improvements. All work to be done in Liberty County.

PRE-QUALIFICATION REQUIRED TO BID ON THIS PROJECT

**Call Order: 001 Proposal: E3W87**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44573515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44573515201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	387.100
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	32.000
	0102- 60-	WORK ZONE SIGN	ED	6,150.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	83,662.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	628.000
	0102-115-	TYPE III BARRICADE	ED	450.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	150.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,492.000
	0107- 1-	LITTER REMOVAL	AC	284.260
	0107- 2-	MOWING	AC	246.780
	0110- 1- 1	CLEARING & GRUBBING (44573515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	345.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	25.000
	0120- 1-	REGULAR EXCAVATION	CY	195.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	134.800
	0160- 4-	TYPE B STABILIZATION	SY	250.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	83.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	542.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	702.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	35,512.000

**Call Order: 001 Proposal: E3W87**

ALT	Item	Description	Unit	Quantity
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	83,758.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	132.200
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	12,214.600
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	40.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	31.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	4.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0440- 1- 50	UNDERDRAIN, TYPE V	LF	73.000
	0440- 73- 2	UNDERDRAIN OUTLET PIPE, 6"	LF	135.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	312.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	34.200
	0524- 1- 3	CONCRETE DITCH PAVEMENT, NON REINFORCED, 5"	SY	345.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	4.000
	0530- 74-	BEDDING STONE	TN	2.900
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,482.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	15,953.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,474.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	23.650
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	900.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	238.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.114
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	8.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	15.358
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	308.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	5.238
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44573515201)	LS	1.000
	<b>Section 0002 Signing</b>			
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	15.408
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	13.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	8.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	3.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,737.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44573515201)	LS	1.000

**Call Order: 001 Proposal: E3W87**

ALT	Item	Description	Unit	Quantity
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	119.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.057
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	8.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	154.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	34.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT RAILROAD DYNAMIC ENVELOPE	LF	450.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	11.825
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	7.679
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	2.619