

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03240208	Call Order: 002	Proposal: E3X12	District:03
Counties:	LEON			
Road Name:	RESURFACING			
Limits:	55060000			
Project(s):	42693735201(*)	Federal Aid No: N/A		
Project(s):	42693735202	Federal Aid No: N/A		
Project(s):	42693735203	Federal Aid No: N/A		
Total Roadway Length:	23.706 Miles	Contract Days:	360	
Total Bridge Length:	0.000 Miles	Letting Date:	02/08/24	
Total Proposal Length:	23.706 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Day Flexible	
Proposal Budget Estimate:	\$10,715,842.00			

Please read the full advertisement

Description:

The Improvements under this District Contract for FPID 426937-3-52-01 consist of milling and resurfacing, minor widening, minor drainage, sidewalk, curb ramps, signing and pavement marking, and signalization, and for FPID 426937-3-52-02 and FPID 426937-3-52-03 consist of utility manhole and valve adjustments along SR 10 (US 90/W. Tennessee Street) from CR 1581 (Aeon Church Road) to Ocala Road, in Leon County.

PRE-QUALIFICATION IS REQUIRED TO BID ON CONTRACT

Call Order: 002 Proposal: E3X12

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (42693735201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42693735201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	648.000
	0102- 60-	WORK ZONE SIGN	ED	17,784.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	121,904.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	108,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	720.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,216.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	3,240.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	3,240.000
	0102-115-	TYPE III BARRICADE	ED	2,880.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,232.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	172.000
	0107- 1-	LITTER REMOVAL	AC	539.640
	0107- 2-	MOWING	AC	470.750
	0110- 1- 1	CLEARING & GRUBBING (42693735201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,015.000
	0120- 1-	REGULAR EXCAVATION	CY	233.700
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	465.500

Call Order: 002 Proposal: E3X12

ALT	Item	Description	Unit	Quantity
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	272.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	81,487.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	110,236.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	1,162.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	9,230.100
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	13,378.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	58.500
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	1.000
	0425- 1-481	INLETS, CURB, TYPE 8, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	4.000
	0425- 5-	MANHOLE, ADJUST	EA	15.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	31.000
	0425- 6-	VALVE BOXES, ADJUST	EA	36.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	80.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	18.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	11.000
	0430-982-121	MITERED END SECTION, OPTIONAL ROUND, 12" CD	EA	1.000
	0430-982-123	MITERED END SECTION, OPTIONAL ROUND, 15" CD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	1.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY, 42" TYPE 1	LF	224.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	275.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,044.000
	0520- 1- 12	CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE	LF	226.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,673.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,017.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	117.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,640.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	14.700
	0530- 74-	BEDDING STONE	TN	10.500
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,733.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	258.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	2.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	6.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,147.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	8.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	6.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	9,729.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	12,338.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	23.640

Call Order: 002 Proposal: E3X12

ALT	Item	Description	Unit	Quantity
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.870
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	21,788.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	3,886.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	3,802.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	14.490
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.802
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	658.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	1,076.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	14.552
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	732.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.384
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	2.746
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42693735201)	LS	1.000
Section 0002	Signing			
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	252.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	45.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	35.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	17.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	77.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	21.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	100.000
	0704- 1- 1	TUBULAR MARKER, DURABLE, 36" WHITE POST	EA	40.000
	0704- 1- 2	TUBULAR MARKER, DURABLE, 36" YELLOW POST	EA	207.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	45.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	6,463.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	2,202.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42693735201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.943
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	11,063.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,972.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,934.000

Call Order: 002 Proposal: E3X12

ALT	Item	Description	Unit	Quantity
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.241
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	353.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	86.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	307.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.386
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	5,135.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	68.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	36.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	11.756
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 1C-30 SKIP OR 3-9 LANE DROP	GM	7.241
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	7.198
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	652.000
Section 0003 Signalization				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	4.030
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	9.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,810.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	8,492.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	9.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	9.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	350.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	157.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	36.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	21.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	25.000
	0649- 21- 8	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 50'-40'	EA	1.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	4.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	4.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	31.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	5.000

Call Order: 002 Proposal: E3X12

ALT	Item	Description	Unit	Quantity
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	8.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	22.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	28.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	88.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	56.000
	0660- 4- 51	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY CABINET EQUIPMENT	EA	1.000
	0660- 4- 52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	2.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	62.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	20.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	9.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	14.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	2.000