

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

|                           |                 |                            |                   |             |
|---------------------------|-----------------|----------------------------|-------------------|-------------|
| Letting:                  | 03240111        | Call Order: 002            | Proposal: E3X02   | District:03 |
| Counties:                 | WALTON          |                            |                   |             |
| Road Name:                | RESURFACING     |                            |                   |             |
| Limits:                   | 60070000        |                            |                   |             |
| Project(s):               | 44366115201(*)  | Federal Aid No:            | N/A               |             |
| Project(s):               | 44366125201     | Federal Aid No:            | N/A               |             |
| Project(s):               | 44366125202     | Federal Aid No:            | N/A               |             |
| Total Roadway Length:     | 28.486 Miles    | Contract Days:             | 395               |             |
| Total Bridge Length:      | 0.030 Miles     | Letting Date:              | 01/11/24          |             |
| Total Proposal Length:    | 28.516 Miles    | Contract Execution Days:   | 10                |             |
|                           |                 | Special Start Date:        | N/A               |             |
|                           |                 | Aquis/Flexible Start Time: | 120 Days Flexible |             |
| Proposal Budget Estimate: | \$18,028,305.00 |                            |                   |             |

Please read the full advertisement

**Description:**

The Improvements under this District Contract consist of FPID 443661-1-52-01, the milling and resurfacing of SR 83 from N of CR 185 to Alabama State Line in Walton County, including overbuild, radius widening, guardrail upgrades, mitered end section replacements, curb and flume reconstruction, bridge joint repair for Bridge No. 600100, signing and pavement markings, and minor flashing signal improvements; FPID 443661-2-52-01, the milling and resurfacing of SR 83 from SR 10 (US 90) to N of CR 185 (Gum Creek Church Road) in Walton County, including overbuild, right turn lane and shoulder widening, radius widening, sidewalk and curb ramp construction, guardrail replacements, drainage improvements, signing and pavement markings, and signalization with strain poles; and FPID 443661-2-52-02 involves utility manhole and valve box adjustments for the City of DeFuniak Springs in Walton County.

Pre-Qualification is required to bid on this project.

**Call Order: 002 Proposal: E3X02**

| ALT                            | Item        | Description   | Unit | Quantity    |
|--------------------------------|-------------|---|------|-------------|
| <b>Section 0001 Structures</b> |             |   |      |             |
|                                | 0458- 1- 21 | BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD | LF   | 246.000     |
|                                | 0458- 2-    | POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT                            | CF   | 55.200      |
| <b>Section 0002 Roadway</b>    |             |   |      |             |
|                                | 0101- 1-    | MOBILIZATION (44366115201)  | LS   | 1.000       |
|                                | 0101- 1-    | MOBILIZATION (44366125201)  | LS   | 1.000       |
|                                | 0102- 1-    | MAINTENANCE OF TRAFFIC (44366115201)                                      | LS   | 1.000       |
|                                | 0102- 1-    | MAINTENANCE OF TRAFFIC (44366125201)                                      | LS   | 1.000       |
|                                | 0102- 2-200 | SPECIAL DETOUR- TEMPORARY PAVEMENT (44366125201)                          | LS   | 1.000       |
|                                | 0102- 2-300 | SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44366125201)                    | LS   | 1.000       |
|                                | 0102- 14-   | TRAFFIC CONTROL OFFICER   | HR   | 72.000      |
|                                | 0102- 60-   | WORK ZONE SIGN  | ED   | 43,612.000  |
|                                | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD                    | ED   | 269,433.000 |
|                                | 0102- 74- 8 | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)    | FD   | 58,500.000  |
|                                | 0102- 99-   | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY                               | ED   | 2,807.000   |
|                                | 0102-104-   | TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION                     | ED   | 395.000     |

**Call Order: 002 Proposal: E3X02**

| ALT | Item         | Description   | Unit | Quantity    |
|-----|--------------|---|------|-------------|
|     | 0102-107- 1  | TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION     | ED   | 395.000     |
|     | 0102-115-    | TYPE III BARRICADE  | ED   | 1,580.000   |
|     | 0102-150- 2  | RADAR SPEED DISPLAY UNIT                                      | ED   | 1,450.000   |
|     | 0104- 10- 3  | SEDIMENT BARRIER  | LF   | 29,665.000  |
|     | 0104- 11-    | FLOATING TURBIDITY BARRIER                                    | LF   | 335.000     |
|     | 0104- 18-    | INLET PROTECTION SYSTEM                                       | EA   | 48.000      |
|     | 0107- 1-     | LITTER REMOVAL  | AC   | 2,102.630   |
|     | 0107- 2-     | MOWING  | AC   | 2,102.630   |
|     | 0110- 1- 1   | CLEARING & GRUBBING (44366115201)                             | LS   | 1.000       |
|     | 0110- 1- 1   | CLEARING & GRUBBING (44366125201)                             | LS   | 1.000       |
|     | 0110- 4- 10  | REMOVAL OF EXISTING CONCRETE                                  | SY   | 242.000     |
|     | 0120- 1-     | REGULAR EXCAVATION  | CY   | 448.900     |
|     | 0120- 2- 2   | BORROW EXCAVATION, TRUCK MEASURE                              | CY   | 64.600      |
|     | 0120- 6-     | EMBANKMENT  | CY   | 321.100     |
|     | 0120- 71-    | REGULAR EXCAVATION (3-R PROJECTS ONLY) (44366115201)          | LS   | 1.000       |
|     | 0160- 4-     | TYPE B STABILIZATION  | SY   | 2,818.000   |
|     | 0285-701-    | OPTIONAL BASE, BASE GROUP 01                                  | SY   | 390.000     |
|     | 0285-703-    | OPTIONAL BASE, BASE GROUP 03                                  | SY   | 174.000     |
|     | 0285-706-    | OPTIONAL BASE, BASE GROUP 06                                  | SY   | 1,489.000   |
|     | 0327- 70- 1  | MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH               | SY   | 542.000     |
|     | 0327- 70- 4  | MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH               | SY   | 1,505.000   |
|     | 0327- 70- 5  | MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH               | SY   | 120,855.000 |
|     | 0327- 70- 6  | MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH           | SY   | 156,307.000 |
|     | 0327- 70- 8  | MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH           | SY   | 873.000     |
|     | 0327- 70- 11 | MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH           | SY   | 300.000     |
|     | 0327- 70- 17 | MILLING EXISTING ASPHALT PAVEMENT, 3 1/4" AVG DEPTH           | SY   | 570.000     |
|     | 0327- 70- 19 | MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH             | SY   | 2,115.000   |
|     | 0334- 1- 52  | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22              | TN   | 17,029.100  |
|     | 0334- 1- 53  | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22              | TN   | 12,745.300  |
|     | 0337- 7- 81  | ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22 | TN   | 19,044.900  |
|     | 0337- 7- 83  | ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22 | TN   | 13,425.600  |
|     | 0339- 1-     | MISCELLANEOUS ASPHALT PAVEMENT                                | TN   | 168.800     |
|     | 0425- 1-201  | INLETS, CURB, TYPE 9, <10'                                    | EA   | 1.000       |
|     | 0425- 1-521  | INLETS, DT BOT, TYPE C,<10'                                   | EA   | 1.000       |
|     | 0425- 1-561  | INLETS, DT BOT, TYPE F, <10'                                  | EA   | 1.000       |
|     | 0425- 2- 61  | MANHOLES, P-8, <10'   | EA   | 1.000       |
|     | 0425- 5-     | MANHOLE, ADJUST   | EA   | 5.000       |
|     | 0425- 5- 1   | MANHOLE, ADJUST, UTILITIES                                    | EA   | 6.000       |
|     | 0425- 6-     | VALVE BOXES, ADJUST   | EA   | 10.000      |
|     | 0425- 14- 1  | GRATE FOR EXISTING DRAINAGE STRUCTURE, FURNISH AND INSTALL    | SF   | 14.000      |
|     | 0430-174-115 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD                 | LF   | 8.000       |
|     | 0430-174-118 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD                 | LF   | 46.000      |

**Call Order: 002 Proposal: E3X02**

| ALT | Item         | Description   | Unit | Quantity   |
|-----|--------------|---|------|------------|
|     | 0430-174-124 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD   | LF   | 65.000     |
|     | 0430-174-218 | PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD                            | LF   | 8.000      |
|     | 0430-175-112 | PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD   | LF   | 4.000      |
|     | 0430-175-118 | PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD   | LF   | 79.000     |
|     | 0430-175-124 | PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD   | LF   | 8.000      |
|     | 0430-175-215 | PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 15"S/CD                                     | LF   | 30.000     |
|     | 0430-175-218 | PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD                                     | LF   | 131.000    |
|     | 0430-518-100 | STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND                                   | EA   | 2.000      |
|     | 0430-984-123 | MITERED END SECTION, OPTIONAL ROUND, 15" SD   | EA   | 1.000      |
|     | 0430-984-125 | MITERED END SECTION, OPTIONAL ROUND, 18" SD   | EA   | 7.000      |
|     | 0430-984-129 | MITERED END SECTION, OPTIONAL ROUND, 24" SD   | EA   | 4.000      |
|     | 0430-984-625 | MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD                                      | EA   | 3.000      |
|     | 0520- 1- 10  | CONCRETE CURB & GUTTER, TYPE F  | LF   | 3,854.000  |
|     | 0522- 1-     | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK   | SY   | 112.000    |
|     | 0522- 2-     | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK   | SY   | 91.000     |
|     | 0524- 1- 2   | CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"   | SY   | 242.000    |
|     | 0527- 2-     | DETECTABLE WARNINGS   | SF   | 122.000    |
|     | 0530- 3- 4   | RIPRAP, RUBBLE, F&I, DITCH LINING   | TN   | 4.900      |
|     | 0536- 1- 1   | GUARDRAIL -ROADWAY, GENERAL TL-3  | LF   | 2,316.000  |
|     | 0536- 7- 3   | SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT                                      | EA   | 3.000      |
|     | 0536- 8-122  | GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3         | EA   | 2.000      |
|     | 0536- 8-123  | GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING              | EA   | 2.000      |
|     | 0536- 73-    | GUARDRAIL REMOVAL   | LF   | 1,629.000  |
|     | 0536- 85- 20 | GUARDRAIL END TREATMENT- TRAILING ANCHORAGE   | EA   | 3.000      |
|     | 0536- 85- 24 | GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL   | EA   | 14.000     |
|     | 0570- 1- 1   | PERFORMANCE TURF  | SY   | 254.000    |
|     | 0570- 1- 2   | PERFORMANCE TURF, SOD   | SY   | 31,736.000 |
|     | 0570- 1- 3   | PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010                            | SY   | 27,717.000 |
|     | 0706- 1- 3   | RAISED PAVEMENT MARKER, TYPE B  | EA   | 12,061.000 |
|     | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"                                       | GM   | 79.582     |
|     | 0710- 11-102 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"      | GM   | 0.086      |
|     | 0710- 11-103 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"             | GM   | 0.436      |
|     | 0710- 11-124 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"              | LF   | 194.000    |
|     | 0710- 11-125 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"           | LF   | 1,848.000  |
|     | 0710- 11-141 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6" | GM   | 0.346      |
|     | 0710- 11-160 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL                               | EA   | 4.000      |
|     | 0710- 11-170 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS  | EA   | 76.000     |

**Call Order: 002 Proposal: E3X02**

| ALT                         | Item         | Description   | Unit | Quantity  |
|-----------------------------|--------------|---|------|-----------|
|                             | 0710- 11-180 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE  | LF   | 32.000    |
|                             | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"  | GM   | 56.730    |
|                             | 0710- 11-224 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"                       | LF   | 628.000   |
|                             | 0710- 11-231 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"   | GM   | 31.253    |
|                             | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44366115201)  | LS   | 1.000     |
|                             | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44366125201)  | LS   | 1.000     |
| <b>Section 0003 Signing</b> |              |   |      |           |
|                             | 0546- 72- 3  | GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL  | GM   | 55.638    |
|                             | 0650- 2-109  | VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED | EA   | 16.000    |
|                             | 0700- 1- 11  | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF   | AS   | 48.000    |
|                             | 0700- 1- 12  | SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF  | AS   | 6.000     |
|                             | 0700- 1- 50  | SINGLE POST SIGN, RELOCATE  | AS   | 5.000     |
|                             | 0700- 1- 60  | SINGLE POST SIGN, REMOVE  | AS   | 18.000    |
|                             | 0700- 1-111  | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF                                 | EA   | 43.000    |
|                             | 0700- 1-112  | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF                                    | EA   | 2.000     |
|                             | 0700- 1-500  | SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE  | EA   | 6.000     |
|                             | 0700- 1-600  | SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE  | EA   | 33.000    |
|                             | 0700- 3-101  | SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF   | EA   | 9.000     |
|                             | 0700- 3-501  | SIGN PANEL, RELOCATE, UP TO 12 SF   | EA   | 8.000     |
|                             | 0705- 10- 1  | OBJECT MARKER, TYPE 1   | EA   | 15.000    |
|                             | 0705- 10- 2  | OBJECT MARKER, TYPE 2   | EA   | 64.000    |
|                             | 0706- 1- 3   | RAISED PAVEMENT MARKER, TYPE B  | EA   | 4,834.000 |
|                             | 0710- 90-    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44366115201)  | LS   | 1.000     |
|                             | 0710- 90-    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44366125201)  | LS   | 1.000     |
|                             | 0711- 11-102 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND                            | GM   | 0.043     |
|                             | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT                               | LF   | 1,150.000 |
|                             | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS                                 | LF   | 97.000    |
|                             | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK                                | LF   | 924.000   |
|                             | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"                          | GM   | 0.173     |
|                             | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL   | EA   | 2.000     |
|                             | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW   | EA   | 38.000    |
|                             | 0711- 11-180 | THERMOPLASTIC, STANDARD, WHITE, YIELD LINE  | LF   | 16.000    |
|                             | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON                                   | LF   | 314.000   |
|                             | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK   | LF   | 473.000   |
|                             | 0711- 14-160 | THERMOPLASTIC, PREFORMED, WHITE, MESSAGE  | EA   | 7.000     |
|                             | 0711- 14-170 | THERMOPLASTIC, PREFORMED, WHITE, ARROW  | EA   | 7.000     |
|                             | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"  | GM   | 39.791    |

**Call Order: 002 Proposal: E3X02**

| ALT                               | Item         | Description  | Unit | Quantity |
|-----------------------------------|--------------|--|------|----------|
|                                   | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"  | GM   | 24.084   |
|                                   | 0711- 16-231 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"   | GM   | 10.952   |
|                                   | 0711- 17- 1  | THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN                      | SF   | 508.000  |
|                                   | 0713-103-101 | PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES  | GM   | 0.107    |
|                                   | 0713-103-201 | PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES   | GM   | 0.051    |
|                                   | 0713-103-231 | PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES                               | GM   | 0.028    |
| <b>Section 0004 Signalization</b> |              |  |      |          |
|                                   | 0611- 2- 1   | ITSFM LOCATION DOCUMENTATION- INTERSECTION   | EA   | 2.000    |
|                                   | 0630- 2- 11  | CONDUIT, FURNISH & INSTALL, OPEN TRENCH  | LF   | 933.000  |
|                                   | 0630- 2- 12  | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE   | LF   | 268.000  |
|                                   | 0632- 7- 1   | SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL                                     | PI   | 2.000    |
|                                   | 0634- 4-152  | SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL   | PI   | 1.000    |
|                                   | 0634- 4-153  | SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX  | PI   | 1.000    |
|                                   | 0634- 5- 1   | FIBERGLASS INSULATOR, FURNISH & INSTALL  | LF   | 84.000   |
|                                   | 0635- 2- 11  | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE   | EA   | 16.000   |
|                                   | 0639- 1-112  | ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY               | AS   | 2.000    |
|                                   | 0639- 2- 1   | ELECTRICAL SERVICE WIRE, FURNISH & INSTALL   | LF   | 74.000   |
|                                   | 0639- 3- 11  | ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT   | EA   | 2.000    |
|                                   | 0641- 2- 12  | PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE   | EA   | 2.000    |
|                                   | 0641- 2- 18  | PRESTRESSED CONCRETE POLE, F&I, TYPE P-VIII  | EA   | 6.000    |
|                                   | 0650- 1- 14  | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY                                 | AS   | 8.000    |
|                                   | 0650- 1- 15  | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 2-4 WAYS                              | AS   | 4.000    |
|                                   | 0650- 2-109  | VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED | EA   | 8.000    |
|                                   | 0660- 1-110  | LOOP DETECTOR INDUCTIVE, F&I, TYPE 10  | EA   | 4.000    |
|                                   | 0660- 2-101  | LOOP ASSEMBLY- F&I, TYPE A   | AS   | 1.000    |
|                                   | 0660- 2-102  | LOOP ASSEMBLY, F&I, TYPE B   | AS   | 4.000    |
|                                   | 0660- 2-106  | LOOP ASSEMBLY, F&I, TYPE F   | AS   | 3.000    |
|                                   | 0670- 5-111  | TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION   | AS   | 2.000    |
|                                   | 0682- 1-133  | ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION                            | EA   | 2.000    |
|                                   | 0684- 6- 12  | WIRELESS COMMUNICATION DEVICE, FURNISH & INSTALL ETHERNET SUBSCRIBER UNIT                              | EA   | 2.000    |
|                                   | 0685- 1- 14  | UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION WITH CABINET               | EA   | 2.000    |
|                                   | 0695- 1- 1   | TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL                                   | EA   | 2.000    |
|                                   | 0695- 6- 12  | TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS                            | EA   | 2.000    |
|                                   | 0700- 3-201  | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF  | EA   | 8.000    |
|                                   | 0700- 5- 21  | INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF                             | EA   | 4.000    |

**Call Order: 002 Proposal: E3X02**

---

| ALT | Item        | Description  | Unit | Quantity |
|-----|-------------|--|------|----------|
|     | 0700- 5- 22 | INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF | EA   | 4.000    |