

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	03240711	Call Order: 001	Proposal: E3V75	District:03
Counties:	SANTA ROSA			
Road Name:	- BRIDGE-REPAIR/REHABILITATION			
Limits:	58170000			
Project(s):	42543925201(*)	Federal Aid No: N/A		
Total Roadway Length:	3.498 Miles	Contract Days:	385	
Total Bridge Length:	3.490 Miles	Letting Date:	07/11/24	
Total Proposal Length:	6.988 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Day Flexible	
Proposal Budget Estimate:	\$3,204,068.00			

Please read the full advertisement

**Description:**

The Improvements under this District Contract consist of restore spalled areas in the top of deck and the outside faces of the box girders, clean and seal top of deck with methacrylate, rehabilitate the pier column at Pier 64, and other incidental construction for SR 281 Avalon Blvd. over East Bay, Bridge No. 580174 in Santa Rosa County.

**PREQUALIFICATION IS REQUIRED TO BID ON THIS PROJECT**

Marine General Liability Insurance as referenced in Section 7-13.5 of the FDOT Standard Specifications may be required if any work under this Contract is performed using vessel(s)\*. Prior to the Contract execution, Contractor shall provide written certification to the Department if no vessel(s) will be used for the work.

\* Vessel: a watercraft or other artificial contrivance, whether motorized or non-motorized, used to perform some or all of the work, as well as any incidental work related to the project, which includes, but is not limited to, barges, dredges, mobile offshore drilling units, floating cranes, tugboats, ferries, and any watercraft used to transport construction workers, materials, or equipment at the project.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 001 Proposal: E3V75**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	161.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	7.400
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	71.000
	0413-151-	METHACRYLATE MONOMER	GA	7,386.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	738,600.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (42543925201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42543925201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	656.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	4,350.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	19,090.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,596.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	6.996
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	6.996
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42543925201)	LS	1.000
<b>Section 0003 Signing</b>				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	7,388.000
	0918-712-100	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 6"	GM	6.996
	0918-712-110	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 6"	GM	6.996