

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03240711 Call Order: 003 Proposal: E3X10 District:03
Counties: JACKSON
Road Name: SR 10 (US 90) - RESURFACING
Limits: 53020000
Project(s): 41537525201(*) Federal Aid No: N/A
Total Roadway Length: 10.252 Miles Contract Days: 245
Total Bridge Length: 0.000 Miles Letting Date: 07/11/24
Total Proposal Length: 10.252 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 30 Day Flexible
Proposal Budget Estimate: \$7,490,120.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of milling and resurfacing SR 10 (US 90) from east of SR 71 to beginning of 4 lane west of Grand Ridge in Jackson County. Improvements also include minor earthwork on shoulders in areas of cross slope correction, drainage, signing, pavement markings, and maintenance of traffic.

PREQUALIFICATION IS REQUIRED TO BID ON THIS PROJECT.

Call Order: 003 Proposal: E3X10

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (41537525201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (41537525201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	590.200
	0102- 60-	WORK ZONE SIGN	ED	13,720.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	84,091.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	504.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	245.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,310.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	16.000
	0107- 1-	LITTER REMOVAL	AC	1,605.560
	0107- 2-	MOWING	AC	1,541.200
	0110- 1- 1	CLEARING & GRUBBING (41537525201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	152.500
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (41537525201)	LS	1.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	2,029.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	46,407.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	133,973.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	11,676.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	15,149.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	25.600
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	36.000

Call Order: 003 Proposal: E3X10

ALT	Item	Description	Unit	Quantity
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	20.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	5.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	294.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	255.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 1	PERFORMANCE TURF	SY	952.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	26,958.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,559.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	18.742
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.053
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	273.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	482.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	9.558
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	764.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	6.575
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (41537525201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	27.398
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	27.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	9.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,559.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (41537525201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.053
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	273.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	482.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	764.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	11.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	18.742
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	9.558
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	6.575
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	28.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 11	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 1 LOOP	EA	2.000