

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03240613	Call Order: 002	Proposal: E3X17	District:03
Counties:	ESCAMBIA			
Road Name:	SR 297 FROM SR 10A (US 90) TO N OF SR 173 - RESURFACING			
Limits:	48190000			
Project(s):	44758915201(*)	Federal Aid No: N/A		
Project(s):	44758915202	Federal Aid No: N/A		
Total Roadway Length:	4.052 Miles	Contract Days:	175	
Total Bridge Length:	0.000 Miles	Letting Date:	06/13/24	
Total Proposal Length:	4.052 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days Flexible	
Proposal Budget Estimate:	\$2,649,734.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of FPID 447589-1-52-01: milling and resurfacing, turn lane widening, intersection improvements, signing and pavement markings and signalization along SR 297 from SR 10A (US 90) Mobile Hwy to N of SR 173 Blue Angel Pkwy, and FPID 447589-1-52-02: utility work by highway contractor along SR 297 from SR 10A (US 90) Mobile Hwy to N of SR 173 Blue Angel Pkwy in Escambia County, Florida .

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 002 Proposal: E3X17

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44758915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44758915201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44758915201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	120.000
	0102- 60-	WORK ZONE SIGN	ED	6,791.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	12,223.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,660.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	245.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	579.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	350.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	350.000
	0102-115-	TYPE III BARRICADE	ED	9.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	36.000
	0107- 1-	LITTER REMOVAL	AC	51.570
	0107- 2-	MOWING	AC	51.570
	0110- 1- 1	CLEARING & GRUBBING (44758915201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	317.000
	0120- 1-	REGULAR EXCAVATION	CY	69.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	230.300
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	271.000

Call Order: 002 Proposal: E3X17

ALT	Item	Description	Unit	Quantity
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	15,006.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	36,316.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	27.900
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	3,025.700
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	3,571.500
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	279.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	197.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	124.000
	0527- 2-	DETECTABLE WARNINGS	SF	338.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,826.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,372.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.142
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.302
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,405.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	272.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	985.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	2.079
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.289
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	71.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.488
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	151.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.297
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.054
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44758915201)	LS	1.000
Section 0002	Signing			
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	38.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	3.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	39.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	3.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,372.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44758915201)	LS	1.000

Call Order: 002 Proposal: E3X17

ALT	Item	Description	Unit	Quantity
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,405.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	272.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	296.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.289
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	68.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	19.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	151.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.054
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	689.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	3.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	3.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.142
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.302
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 1C -30 SKIP OR 3-9 LANE DROP	GM	2.079
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.488
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.297
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	103.000
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,473.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	240.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	13.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	9.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	4.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	16.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	6.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	2.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	4.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	20.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	9.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	7.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	3.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	4.000

Call Order: 002 Proposal: E3X17

ALT	Item	Description	Unit	Quantity
	0670- 5-112	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 2 PREEMPTION	AS	2.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	2.000
	0684- 1- 4	MANAGED FIELD ETHERNET SWITCH, RELOCATE	EA	2.000
	0685- 1- 14	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION WITH CABINET	EA	2.000