Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03240613 Call Order: 005 Proposal: E3Y05 District:03

Counties: HOLMES

Road Name: PONCE DE LEON MAINT - WDD RESHAPE DITCH AND REWORK SHLDR

Limits: Midpoint

Project(s): 42214337223(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	THRU 6/30/25
Total Bridge Length:	0.000 Miles	Letting Date:	06/13/24
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 DAYS

Proposal Budget Estimate: $150,000.00

Please read the full advertisement

Description:

The Improvements under this Work Document Driven Contract consist of reshaping ditches and reworking shoulders on SR 8 (US Interstate 10) in Holmes County. These ditches are non-typical and should be re-graded to +/- 3 inches of the original flow line to create a free and unobstructed flow of drainage water. For the purposes of this contract, the original flow line is considered to be the linear projection along the ditch bottom between the invert elevations of immediately adjacent drainage structures. Spoil material removed from ditches and shoulders shall be relocated to FDOT storage pits in Caryville. Mobilization and Maintenance of Traffic are incidental to the pay items listed.

This contract has a budgetary estimate of $150,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder, however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

A Proposal Guaranty will not be required on indefinite quantity contracts, such as work document driven contracts, with a Departments advertised estimate amount of $150,000 or less regardless of the bid amount.

Call Order: 005 Proposal: E3Y05

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	1.000
	0104- 10- 3	SEDIMENT BARRIER	LF	75.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	10.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	5.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	27,500.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	400.000
	E573- 1-	HYDRO-SEEDING - APPLICATION OF SLURRY INCLUDING WOOD FIBER, SEED, FERTILIZER, TACKIFIER & DYE	SY	150.000
	E577- 70-	SHOULDER REWORK	SY	27,500.000
	E577- 71-	BLADING PAVED SHOULDER, UP TO 24" BEYOND PAVEMENT	LF	100.000