

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 03240314 Call Order: 002 Proposal: E3W06 District:03  
Counties: WASHINGTON  
Road Name: - BRIDGE-REPAIR/REHABILITATION  
Limits: 61001000  
Project(s): 22283255201(\*) Federal Aid No: N/A  
Total Roadway Length: 0.000 Miles Contract Days: 100  
Total Bridge Length: 0.000 Miles Letting Date: 03/14/24  
Total Proposal Length: 0.000 Miles Contract Execution Days: 10  
Special Start Date: N/A  
Aquis/Flexible Start Time: 30 Days Flexible  
Proposal Budget Estimate: \$576,026.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of sealing the deck and approach slabs and repairing polymer headers and pourable joints of bridge on SR 8 (I-10) Over Choctawhatchee River, Bridge No. 610047, in Washington and Holmes Counties.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 002 Proposal: E3W06**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0413-151-	METHACRYLATE MONOMER	GA	816.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	81,600.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	82.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	12.200
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (22283255201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (22283255201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,000.000
	0102- 60-	WORK ZONE SIGN	ED	1,000.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	8,900.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	100.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	200.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	200.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	200.000
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	0.386
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.386
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.386
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	52.000
	0918-712-100	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 6"	GM	0.386
	0918-712-110	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 6"	GM	0.386
	0918-712-130	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, BLACK, 10-30 SKIP 6"	GM	0.386
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (22283255201)	LS	1.000