

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	03240509	Call Order: 001	Proposal: E3W76	District:03
Counties:	ESCAMBIA			
Road Name:	RESURFACING			
Limits:	48003000			
Project(s):	42693425201(*)	Federal Aid No:	N/A	
Project(s):	42693425202	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	240	
Total Bridge Length:	0.000 Miles	Letting Date:	05/09/24	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days Flexible	
Proposal Budget Estimate:	\$3,938,187.00			

Please read the full advertisement

**Description:**

The Improvements under this District Contract consist of resurfacing, restoration, and rehabilitation (RRR) of SR 289 (9th Ave.) from SR 742 (Creighton Rd.) to CR 290 (Olive Rd.) in Escambia County. The project also includes milling and resurfacing, shoulder treatment, drainage improvements, curb and gutters, traffic and pedestrian signals, highway signing, pavement markings, sidewalk replacement, and other incidental construction under FPID 426934-2-52-01. Utility manhole and valve adjustments by highway contractor are included under FPID 426934-2-52-02.

PREQUALIFICATION IS REQUIRED TO BID ON THIS PROJECT.

**Call Order: 001 Proposal: E3W76**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (42693425201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42693425201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	312.000
	0102- 60-	WORK ZONE SIGN	ED	8,674.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	14,548.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	9,672.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	630.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	189.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	808.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	960.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	960.000
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	0.013
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.172
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.055
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.401
	0104- 10- 3	SEDIMENT BARRIER	LF	165.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	32.000
	0107- 1-	LITTER REMOVAL	AC	90.480
	0107- 2-	MOWING	AC	90.480

**Call Order: 001 Proposal: E3W76**

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (42693425201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	479.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	15.100
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (42693425201)	LS	1.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	25.400
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	5,536.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	42,899.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	276.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	3,557.800
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	3,348.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	4.100
	0425- 1-910	INLETS, CLOSED FLUME	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	49.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	11.000
	0430-610-233	U-ENDWALL, INDEX 261/430-011, 1:3 SLOPE, 30"PIPE	EA	1.000
	0430-982-120	MITERED END SECTION, OPTIONAL ROUND, 8" CD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	3.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	3.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	237.000
	0515- 4- 1	BULLET RAIL, SINGLE RAIL	LF	569.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	81.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	345.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	221.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	186.000
	0522- 4-	BUS SHELTER PAD- CONCRETE	SY	8.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	160.000
	0527- 2-	DETECTABLE WARNINGS	SF	527.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	7.000
	0530- 74-	BEDDING STONE	TN	5.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	50.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	569.000
	0536- 7- 1	SPECIAL GUARDRAIL POST- DEEP POST FOR SLOPE BREAK CONDITION- TIMBER OR STEEL	EA	9.000
	0536- 73-	GUARDRAIL REMOVAL	LF	110.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	3.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	634.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,504.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.831
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.120
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	953.000

**Call Order: 001 Proposal: E3W76**

ALT	Item	Description	Unit	Quantity
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	150.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,044.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.982
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.065
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.470
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	25.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	87.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.528
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	738.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.577
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.160
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42693425201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	52.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	6.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	36.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	3.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	6.000
	0704- 1- 2	TUBULAR MARKER, DURABLE, 36" YELLOW POST	EA	8.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,150.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	263.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42693425201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	953.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	150.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	275.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.470
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	9.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	71.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	738.000

**Call Order: 001 Proposal: E3W76**

ALT	Item	Description	Unit	Quantity
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.160
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	769.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	16.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	16.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.831
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.120
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",1C-30 SKIP OR 3-9 LANE DROP	GM	1.982
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"-APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.065
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.518
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.577
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	110.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.054
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.105
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.215
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.105
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,224.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	876.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	3.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	42.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	14.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	5.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	3.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	5.000
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	22.000
	0650- 1- 36	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 4 SECTION, 1 WAY	AS	2.000
	0650- 1- 38	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 5 SECTION STRAIGHT, 1 WAY	AS	3.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	14.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	2.000
	0660- 1-111	LOOP DETECTOR INDUCTIVE, F&I, TYPE 11, 4 CH, SS, RM	EA	1.000
	0660- 1-112	LOOP DETECTOR INDUCTIVE, F&I, TYPE 12, 4 CH, SS, RM, TD	EA	2.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000

**Call Order: 001 Proposal: E3W76**

ALT	Item	Description	Unit	Quantity
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	11.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	14.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	3.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	2.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	3.000
	0671- 2- 11	TRAFFIC CONTROLLER WITHOUT CABINET, F&I IN EXISTING CABINET, NEMA	EA	1.000
	0671- 2- 60	TRAFFIC CONTROLLER, REMOVE- CABINET TO REMAIN	EA	1.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0684- 6- 12	WIRELESS COMMUNICATION DEVICE, FURNISH & INSTALL ETHERNET SUBSCRIBER UNIT	EA	3.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	2.000
	0685- 1- 14	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION WITH CABINET	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	8.000
	0700-141-111	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000
<b>Section 0004 Utilities</b>				
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	3.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000