

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 03250410 Call Order: 002 Proposal: E3Y09 District:03  
 Counties: FRANKLIN  
 Road Name: SR 300 CR 300 BEACH DR TO SR 30 (US 98/319) - RESURFACING  
 Limits: 49580000  
 Project(s): 44697425201(\*) Federal Aid No: N/A  
 Total Roadway Length: 1.726 Miles Contract Days: 130  
 Total Bridge Length: 0.000 Miles Letting Date: 04/10/25  
 Total Proposal Length: 1.726 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 30 Day Flexible  
 Proposal Budget Estimate: \$1,756,396.00

Please read the full advertisement

**Description:**

The Improvements under this District Contract consist of milling and resurfacing SR 300 CR 300 Beach Dr to SR 30 (US 98/319); in Franklin County, FL. FPID 446974-2-52-01 includes milling and resurfacing, and sidewalk construction. This Contract also includes restriping Bridge No. 490100.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS CONTRACT

**Call Order: 002 Proposal: E3Y09**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44697425201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44697425201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,936.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	21,664.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	5,590.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	696.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	70.000
	0104- 10- 3	SEDIMENT BARRIER	LF	877.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	248.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	22.000
	0107- 1-	LITTER REMOVAL	AC	93.300
	0107- 2-	MOWING	AC	71.540
	0110- 1- 1	CLEARING & GRUBBING (44697425201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	12.000
	0120- 1-	REGULAR EXCAVATION	CY	76.700
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	32.700
	0160- 4-	TYPE B STABILIZATION	SY	34.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	34.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	1,710.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	20,538.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	14,284.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	216.700

**Call Order: 002 Proposal: E3Y09**

ALT	Item	Description	Unit	Quantity
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	3.800
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	2,872.800
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	6.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	511.000
	0527- 2-	DETECTABLE WARNINGS	SF	300.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,249.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,456.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.096
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	955.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	210.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	767.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	6.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.354
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	30.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.012
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44697425201)	LS	1.000
<b>Section 0002 Signing</b>				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	0.695
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	39.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	8.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	22.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	10.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	10.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	32.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	30.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,228.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44697425201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	955.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	210.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	457.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	6.000

**Call Order: 002 Proposal: E3Y09**

ALT	Item	Description	Unit	Quantity
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	30.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	310.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.096
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.177
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.506
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	31,548.000
	0918-712-100	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 6"	GM	8.174
	0918-712-110	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 6"	GM	3.223
	0918-712-115	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, 10-30 SKIP 6"	GM	3.523