

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03250410 Call Order: 004 Proposal: E3Y28 District:03
Counties: SANTA ROSA
Road Name: SR 4 OVER WILSON BRANCH CREEK AND EAST RELIEF BRIDGE
Limits: 58080000
Project(s): 45443415201(*) Federal Aid No: N/A
Total Roadway Length: 0.398 Miles Contract Days: 120
Total Bridge Length: 0.114 Miles Letting Date: 04/10/25
Total Proposal Length: 0.512 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 30 Days Flex.
Proposal Budget Estimate: \$416,567.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of SR 4 OVER WILSON BRANCH CREEK AND EAST RELIEF. Improvements for this contract include plans for pourable joint and polymer header replacement, maintenance of traffic plans, and any other details required to repair and rehabilitate SR 4 bridges (Bridge No. 580101 and Bridge No. 580102) over Wilson Branch Creek and East Relief in Santa Rosa County.

PRE-QUALIFICATION REQUIRED TO BID ON THIS CONTRACT

Marine General Liability Insurance as referenced in Section 7-13.5 of the FDOT Standard Specifications may be required if any work under this Contract is performed using vessel(s)*. Prior to the Contract execution, Contractor shall provide written certification to the Department if no vessel(s) will be used for the work.

* Vessel: a watercraft or other artificial contrivance, whether motorized or non-motorized, used to perform some or all of the work, as well as any incidental work related to the project, which includes, but is not limited to, barges, dredges, mobile offshore drilling units, floating cranes, tugboats, ferries, and any watercraft used to transport construction workers, materials, or equipment at the project

Call Order: 004 Proposal: E3Y28

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0104- 18-	INLET PROTECTION SYSTEM	EA	34.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	12.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	9.400
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	1,107.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	199.500
	0521- 5- 4	CONCRETE TRAFFIC RAILING- BRIDGE, 32" VERTICAL FACE	LF	6.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (45443415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45443415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,133.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,691.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	166.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	64.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45443415201)	LS	1.000