

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03250213	Call Order: 001	Proposal: E3W68	District:03
Counties:	BAY			
Road Name:	- BRIDGE-REPAIR/REHABILITATION			
Limits:	46040000			
Project(s):	45102815201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.062 Miles	Contract Days:	60	
Total Bridge Length:	0.062 Miles	Letting Date:	02/13/25	
Total Proposal Length:	0.124 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Day Flexible	
Proposal Budget Estimate:	\$177,793.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of SR 75 (US 231) over Bayou George Bridge No. 460079 cleaning and sealing deck with High Molecular Weight Methacrylate (HMWM), and other incidental work in Bay County, Florida (46040).

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <https://www.fdot.gov/equalopportunity/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at <https://www.fdot.gov/equalopportunity/bdi.shtm>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at <https://www.fdot.gov/equalopportunity/bdi.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to SmallBusiness@dot.state.fl.us

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 001 Proposal: E3W68

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0413-151-	METHACRYLATE MONOMER	GA	138.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	13,800.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (45102815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45102815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	990.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,696.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	60.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	74.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	120.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	120.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.066
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.066
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.066
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45102815201)	LS	1.000
Section 0003 Signing				
	0918-712-100	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 6"	GM	0.066
	0918-712-110	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 6"	GM	0.066
	0918-712-120	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, 10-30 SKIP 6"	GM	0.066