

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	03250213	Call Order: 003	Proposal: E3X76	District:03
Counties:	WALTON			
Road Name:	SR 20 OVER CHOCTAWHATCHEE RIVER - BRIDGE-REPAIR			
Limits:	60030000			
Project(s):	44546615201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.612 Miles	Contract Days:	245	
Total Bridge Length:	0.612 Miles	Letting Date:	02/13/25	
Total Proposal Length:	1.224 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days Flex.	
Proposal Budget Estimate:	\$2,052,505.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of bridge repair on SR 20 over Choctawhatchee River, bridge number 600105, in Walton County. 445466-1-52-01 includes pile jacket installation, substructure crack repair (epoxy injection) and deck sealing.

Pre-Qualification is required to bid on this project.

Marine General Liability Insurance as referenced in Section 7-13.5 of the FDOT Standard Specifications may be required if any work under this Contract is performed using vessel(s)*. Prior to the Contract execution, Contractor shall provide written certification to the Department if no vessel(s) will be used for the work.

* Vessel: a watercraft or other artificial contrivance, whether motorized or non-motorized, used to perform some or all of the work, as well as any incidental work related to the project, which includes, but is not limited to, barges, dredges, mobile offshore drilling units, floating cranes, tugboats, ferries, and any watercraft used to transport construction workers, materials, or equipment at the project.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 003 Proposal: E3X76

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	2,235.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	57.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	10.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	165.000
	0413-149-	PENETRANT SEALER	GA	5.000
	0413-151-	METHACRYLATE MONOMER	GA	1,422.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	142,120.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	12,469.000
	0457- 1- 22	STANDARD INTEGRAL PILE JACKET, STRUCTURAL, 16.1 to 30.0"	LF	825.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44546615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44546615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	448.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,016.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	81.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	32.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	1.223
	0102-913- 32	REMOVABLE TAPE, YELLOW, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	0.612
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	81.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.223
	0713-103-281	PERMANENT TAPE, YELLOW, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.612
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44546615201)	LS	1.000