

Call Order: 002 Proposal: E3X91

ALT	Item	Description	Unit	Quantity
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	33,857.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	14,375.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	2,875.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	5,999.100
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	2.000
	0425- 1-713	INLETS, GUTTER, TYPE V, J BOT, <10'	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	16.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	471.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	648.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	193.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	408.000
	0525- 1-	ASPHALTIC CONCRETE CURB- TO REMAIN	LF	222.000
	0527- 2-	DETECTABLE WARNINGS	SF	674.000
	0570- 1- 1	PERFORMANCE TURF	SY	895.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	6,814.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	232.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.185
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.185
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43356925201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	20.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	22.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	756.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43356925201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,605.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	316.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.019
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	200.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	43.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	43.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.474
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.222
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	603.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	277.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	184.000

Call Order: 002 Proposal: E3X91

ALT	Item	Description	Unit	Quantity
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	14.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,885.000
	0715- 5- 21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	2.000
	0715- 7- 12	LOAD CENTER, F&I, PRIMARY VOLTAGE	EA	3.000
	0715- 61-711	LIGHT POLE COMPLETE, F&I, STD POLE STD FOUNDATION, WILDLIFE SENSITIVE LUMINAIRE, 20' MOUNTING HEIGHT, 8' ARM LENGTH	EA	3.000
	0715- 62-711	LIGHT POLE COMPLETE, F&I, STD POLE SPECIAL FOUNDATION, WILDLIFE SENSITIVE LUMINAIRE, 20' MOUNTING HEIGHT, 8' ARM LENGTH	EA	3.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	6.000