

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	03250710	Call Order: 001	Proposal: E3Y01	District:03
Counties:	WASHINGTON			
Road Name:	- BRIDGE-REPAIR/REHABILITATION			
Limits:	61001000			
Project(s):	45276015201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.511 Miles	Contract Days:	120	
Total Bridge Length:	0.034 Miles	Letting Date:	07/10/25	
Total Proposal Length:	0.545 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Day Flexible	

Proposal Budget Estimate: \$2,769,774.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of replacing the WB approach slab and traffic railing on the east end of the bridge, and minor roadway reconstruction with milling, resurfacing, and pavement markings. Drainage improvements include replacement of shoulder gutter and shoulder gutter inlet tops that are impacted by TTCP operations. Other improvements include replacement of guardrail impacted by TTCP and replacement of the expansion joint adjacent to the new approach slab on SR 8 (I-10) over CR 279 Pate Pond Road Bridge No. 610050 in Washington County.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 001 Proposal: E3Y01

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (45276015201)	LS	1.000
	0400- 7- 1	BRIDGE DECK GROOVING	SY	134.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	8.600
	0400-153-	NON SHRINK GROUT, F&I, MISCELLANEOUS- STRUCTURES REHAB	CF	221.600
	0413-151-	METHACRYLATE MONOMER	GA	13.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	1,201.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	49.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	41.000
	0460- 1- 15	STRUCTURAL STEEL - REHABILITATION, MISCELLANEOUS	LB	29,763.000
	0521- 5-100	CONCRETE TRAFFIC RAILING- BRIDGE, 32" F-SHAPE	LF	61.000
	0916-400- 9	PRECAST APPROACH SLAB UNIT	SF	1,293.000
	0918-349-100	ULTRA HIGH PERFORMANCE CONCRETE (UHPC)	CY	2.400
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (45276015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45276015201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (45276015201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (45276015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	24.000
	0102- 60-	WORK ZONE SIGN	ED	2,027.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,116.000

Call Order: 001 Proposal: E3Y01

ALT	Item	Description	Unit	Quantity
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	836.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	3,964.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,559.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	75.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	11.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	93.000
	0102-115-	TYPE III BARRICADE	ED	53.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	178.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	178.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	2.530
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.506
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	2.852
	0104- 10- 3	SEDIMENT BARRIER	LF	1,005.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0110- 1- 1	CLEARING & GRUBBING (45276015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	192.000
	0120- 1-	REGULAR EXCAVATION	CY	161.300
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	554.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	144.000
	0285-761-	OPTIONAL BASE- GRADED AGGREGATE, 20" THICK, 6" MAXIMUM LIFTS	SY	147.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,666.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	6,490.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	788.300
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	279.600
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	41.300
	0425- 1-705	INLETS, GUTTER, TYPE S, PARTIAL	EA	2.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	458.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	790.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	829.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	823.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,628.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45276015201)	LS	1.000
Section 0003 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.812
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	87.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45276015201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	16.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.345

Call Order: 001 Proposal: E3Y01

ALT	Item	Description	Unit	Quantity
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.073
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.515
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.467
	0918-712-100	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 6"	GM	0.044
	0918-712-110	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 6"	GM	0.044
	0918-712-120	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, 10-30 SKIP 6"	GM	0.044
	0918-712-130	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, BLACK, 10-30 SKIP 6"	GM	0.044