

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	03250313	Call Order: 004	Proposal: E3Y25	District:03
Counties:	LEON			
Road Name:	BRIDGE-REPAIR/REHABILITATION			
Limits:	55003000			
Project(s):	45431115201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.057 Miles	Contract Days:	120	
Total Bridge Length:	0.058 Miles	Letting Date:	03/13/25	
Total Proposal Length:	0.115 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days Flexible	
Proposal Budget Estimate:	\$629,990.00			

Please read the full advertisement

**Description:**

The improvements under this District Contract consist of bridge repair/rehabilitation to include deck seal, spall repair, and expansion joint replacement for SR 261 (Capital Circle NE) over SR 8 (I-10) Bridge No. 550076 in Leon County.

**PRE-QUALIFICATION REQUIRED TO BID ON THIS CONTRACT**

Marine General Liability Insurance as referenced in Section 7-13.5 of the FDOT Standard Specifications may be required if any work under this Contract is performed using vessel(s)\*. Prior to the Contract execution, Contractor shall provide written certification to the Department if no vessel(s) will be used for the work.

\* Vessel: a watercraft or other artificial contrivance, whether motorized or non-motorized, used to perform some or all of the work, as well as any incidental work related to the project, which includes, but is not limited to, barges, dredges, mobile offshore drilling units, floating cranes, tugboats, ferries, and any watercraft used to transport construction workers, materials, or equipment at the project.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 004 Proposal: E3Y25**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	8.900
	0401- 70- 9	RESTORE SPALLED AREAS, VERY RAPID HARDENING MORTAR/CONCRETES	CF	128.300
	0413-151-	METHACRYLATE MONOMER	GA	344.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	34,448.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	256.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (45431115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45431115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	480.000
	0102- 60-	WORK ZONE SIGN	ED	5,712.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	9,960.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	240.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	264.000
	0102-115-	TYPE III BARRICADE	ED	144.000
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	0.186
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.338
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.186
	0102-913- 23	REMOVABLE TAPE, WHITE, 24" STOP BAR	LF	76.000
	0102-913- 29	REMOVABLE TAPE, WHITE, MESSAGE, SYMBOL OR ARROW	EA	14.000
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.131
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	114.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45431115201)	LS	1.000
<b>Section 0003 Signing</b>				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	114.000
	0711- 14-527	THERMOPLASTIC, PREFORMED, 24" WHITE WITH 4" BLACK CONTRAST FOR STOP LINE ON CONCRETE PAVEMENT, 32"	LF	64.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	7.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	11.000
	0918-712-100	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 6"	GM	0.338
	0918-712-110	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 6"	GM	0.131
	0918-712-120	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, 10-30 SKIP 6"	GM	0.186
	0918-712-130	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, BLACK, 10-30 SKIP 6"	GM	0.186