

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 03250313 Call Order: 006 Proposal: E3Y56 District:03  
 Counties: HOLMES, WALTON, WASHINGTON  
 Road Name: PONCE DE LEON MAINT - DITCH CLEARING ROUTINE MAINTENANCE  
 Limits: Midpoint  
 Project(s): 42214337256(\*) Federal Aid No: N/A  
 Total Roadway Length: 0.000 Miles Contract Days: THRU 12/31/250  
 Total Bridge Length: 0.000 Miles Letting Date: 03/13/25  
 Total Proposal Length: 0.000 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 DAYS

Proposal Budget Estimate: \$400,000.00

Please read the full advertisement

**Description:**

The Improvements under this Work Document-Driven Contract consists of the removal and placement of concrete ditch pavement in Holmes, Walton, and a portion of Washington Counties. Some locations will require clearing and grubbing of 6 feet in width on each side of the concrete ditch pavement. Maintenance of Traffic and Mobilization will be incidental to the pay items listed.

This contract has a budgetary estimate of \$400,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder, however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

**Call Order: 006 Proposal: E3Y56**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 CONCRETE PAVEMENT SURFACE REPAIR (SF)</b>				
	0104- 10- 3	SEDIMENT BARRIER	LF	1,000.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	200.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	250.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	60.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	500.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	500.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	250.000
	E110- 2-	CLEARING & GRUBBING	AC	40.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	1,250.000
	E524- 1- 1	CONCRETE DITCH PAVEMENT REPAIR	CY	60.000
	E524- 2- 1	CONCRETE SLOPE PAVEMENT REPAIR	CY	30.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	400.000
	E573- 1-	HYDRO-SEEDING - APPLICATION OF SLURRY INCLUDING WOOD FIBER, SEED, FERTILIZER, TACKIFIER & DYE	SY	10,000.000
	E575- 1-	SODDING	SY	10,000.000
	E577- 70-	SHOULDER REWORK	SY	10,000.000