## Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 03250911 Call Order: 002 Proposal: E3Y90-R0 District:03

Counties: LEON

Road Name: MIDWAY OPS MAINT - URBAN CONCRETE REPAIR - NIGHT WORK

Limits: 55320000

Project(s): 42215127282(\*) Federal Aid No: N/A

Total Roadway Length:0.000 MilesContract Days:12/31/26Total Bridge Length:0.000 MilesLetting Date:09/11/25

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 15 DAYS

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

## Description:

The work under this Work Document Driven Contract, consists of night-time removal, replacement and/or repairs of driveways, sidewalks pipe culverts, ditch pavement, curbs, gutters, and manholes located in urban Leon County as described in the appendices. Other services required to achieve this work include Maintenance of Traffic, adjusting utility features (e.g. manhole rings, water meter boxes, valve risers, etc.), providing erosion control, borrow material or hot mix asphalt, maintaining pedestrian and driveway access, sodding, and watering disturbed areas. Mobilization is incidental to other items listed.

## THIS CONTRACT HAS A BUDGETARY ESTIMATE OF \$500,000.00

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder, however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

## Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

| Call Order: 002 Proposal: E3Y90-R0 |  |      |           |
|------------------------------------|--|------|-----------|
| ALT Item                           | Description  | Unit | Quantity  |
| Section 0001 TRAFFIC               | CONTROL DEVICES CONTROL (MH)   |      |           |
| 0102- 3-                           | COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE                     | CY   | 10.000    |
| 0102- 14-                          | TRAFFIC CONTROL OFFICER  | HR   | 40.000    |
| 0102- 60-                          | WORK ZONE SIGN   | ED   | 1,000.000 |
| 0102- 61-                          | BUSINESS SIGN  | EA   | 10.000    |
| 0102- 74- 1                        | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD                     | ED   | 1,500.000 |
| 0102- 74- 8                        | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)     | FD   | 6,000.000 |
| 0102- 76-                          | ARROW BOARD / ADVANCE WARNING ARROW PANEL                                  | ED   | 75.000    |
| 0102- 99-                          | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY                                | ED   | 10.000    |
| 0102-909-                          | TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS | DA   | 2.000     |
| 0104- 1-                           | ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS                      | SY   | 500.000   |
| 0104- 10- 3                        | SEDIMENT BARRIER   | LF   | 200.000   |
| 0104- 18-                          | INLET PROTECTION SYSTEM  | EA   | 10.000    |
| 0110- 4-10                         | REMOVAL OF EXISTING CONCRETE   | SY   | 1,927.000 |
| 0120- 2- 2                         | BORROW EXCAVATION, TRUCK MEASURE   | CY   | 110.000   |
| 0285-706-                          | OPTIONAL BASE, BASE GROUP 06   | SY   | 10.00     |
| 0334- 1-52                         | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22                           | TN   | 10.000    |
| 0339- 1-                           | MISCELLANEOUS ASPHALT PAVEMENT   | TN   | 10.000    |
| 0425- 5-                           | MANHOLE, ADJUST  | EA   | 10.000    |
| 0425- 6-                           | VALVE BOXES, ADJUST  | EA   | 10.000    |
| 0430-174-118                       | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD                              | LF   | 120.000   |
| 0430-174-124                       | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD                              | LF   | 24.000    |
| 0430-984-125                       | MITERED END SECTION, OPTIONAL ROUND, 18" SD                                | EA   | 5.000     |
| 0430-984-129                       | MITERED END SECTION, OPTIONAL ROUND, 24" SD                                | EA   | 2.000     |
| 0515- 1-41                         | PIPE HANDRAIL - GUIDERAIL, RELOCATE, STEEL                                 | LF   | 10.000    |
| 0515- 1-42                         | PIPE HANDRAIL - GUIDERAIL, RELOCATE, ALUMINUM                              | LF   | 10.000    |
| 0515- 2-311                        | PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1                      | LF   | 10.000    |
| 0515- 2-500                        | PEDESTRIAN / BICYCLE RAILING, RELOCATE                                     | LF   | 10.000    |
| 0520- 1- 7                         | CONCRETE CURB & GUTTER, TYPE E   | LF   | 10.000    |
| 0520- 1-10                         | CONCRETE CURB & GUTTER, TYPE F   | LF   | 300.000   |
| 0520- 3-                           | VALLEY GUTTER- CONCRETE  | LF   | 10.000    |
| 0522- 1-                           | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK                                  | SY   | 1,550.000 |
| 0522- 2-                           | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK                                  | SY   | 200.000   |
| 0524- 1- 2                         | CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"                                | SY   | 110.000   |
| 0527- 2-                           | DETECTABLE WARNINGS  | SF   | 500.000   |
| E102-100-                          | MOT MAINTENANCE SERVICES   | HR   | 450.000   |
| E110- 70-                          | REMOVAL OF FLEXIBLE PAVEMENT   | SY   | 10.00     |
| E425- 73- 7                        | MANHOLE FRAME & COVER  | EA   | 1.000     |
| E570- 9- 1                         | WATER FOR GRASS & PLANTS   | MG   | 1.000     |
| E575- 1-                           | SODDING  | SY   | 700.000   |