

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	03250924	Call Order: 001	Proposal: E3Y84	District:03
Counties:	JACKSON			
Road Name:	US 231 - MISCELLANEOUS CONSTRUCTION			
Limits:	53050000			
Project(s):	45655715201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.256 Miles	Contract Days:	360	
Total Bridge Length:	0.000 Miles	Letting Date:	09/24/25	
Total Proposal Length:	0.256 Miles	Contract Execution Days:	5	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Day Flexible	
Proposal Budget Estimate:	\$12,968,501.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of constructing the SR 75 (US 231) Florida Department of Agriculture Inspection Station from MP 18.005 to MP 18.261 in Jackson County, Florida. Improvements include widening the existing Welcome Center entrance, constructing an asphalt driveway from A.M.E. Road, providing an asphalt employee parking area, constructing ingress/egress concrete ramps along with concrete inspection lanes, constructing two buildings (Administration & Inspection), adding curb and gutter, barrier walls, sidewalk, drainage improvements, ITS, signing & pavement markings, lighting, and other ancillary construction.

PREQUALIFICATION REQUIRED TO BID ON THIS CONTRACT

AWARD AND EXECUTION CONTINGENT UPON BUDGET AVAILABILITY

Call Order: 001 Proposal: E3Y84

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45655715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45655715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,600.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	276.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	8,640.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	720.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,815.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	1.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	92.790
	0107- 2-	MOWING	AC	68.930
	0110- 1- 1	CLEARING & GRUBBING (45655715201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.560
	0110- 21-	TREE PROTECTION BARRIER	LF	2,051.000
	0120- 1-	REGULAR EXCAVATION	CY	2,362.100
	0120- 4-	SUBSOIL EXCAVATION	CY	4,660.700
	0120- 6-	EMBANKMENT	CY	7,071.600
	0160- 4-	TYPE B STABILIZATION	SY	12,708.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	7,233.000

Call Order: 001 Proposal: E3Y84

ALT	Item	Description	Unit	Quantity
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	1,330.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	366.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	201.000
	0350- 3- 5	PLAIN CEMENT CONCRETE PAVEMENT, 8"	SY	111.000
	0350- 3- 7	PLAIN CEMENT CONCRETE PAVEMENT, 9"	SY	7,017.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	10,723.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	7,128.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	68.100
	0400- 0- 13	CONCRETE CLASS NS, STEPS	CY	11.300
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	316.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	1.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	390.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	170.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	5.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	1.000
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	1,495.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	141.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	451.000
	0519- 78-	BOLLARDS	EA	4.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	250.000
	0520- 1- 12	CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE	LF	19.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	145.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	311.000
	0521- 72- 43	SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER	LF	41.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	299.000
	0527- 2-	DETECTABLE WARNINGS	SF	41.000
	0542- 70-	BUMPER GUARDS, CONCRETE	EA	14.000
	0550- 10-110	FENCING, TYPE A, 0.0-5.0', STANDARD	LF	315.000
	0550- 10-241	FENCING, TYPE B, 7.1-8.0', WITH BARBED WIRE ATTACHMENT	LF	20.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	11,116.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45655715201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	3.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	4.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	1.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	2.000

Call Order: 001 Proposal: E3Y84

ALT	Item	Description	Unit	Quantity
	0700- 2-117	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 200.1-300.0 SF	EA	1.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6" FOR PARKING SPACES	LF	260.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	498.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.027
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	1.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID, 6"	LF	40.000
	0711- 14-341	THERMOPLASTIC, PREFORMED, BLACK, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.044
	0711- 14-521	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, SOLID, 6" FOR PARKING SPACES	LF	83.000
	0711- 14-526	THERMOPLASTIC, PREFORMED, 24" WHITE WITH 4" BLACK CONTRAST FOR CROSSWALK ON CONCRETE PAVEMENT, 32"	LF	80.000
	0711- 14-527	THERMOPLASTIC, PREFORMED, 24" WHITE WITH 4" BLACK CONTRAST FOR STOP LINE ON CONCRETE PAVEMENT, 32"	LF	30.000
	0711- 14-528	THERMOPLASTIC, PREFORMED, 12" WHITE WITH 4" BLACK CONTRAST FOR CROSSWALK ON CONCRETE PAVEMENT, 20"	LF	82.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	2.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	3.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.061
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	446.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,537.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	498.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	23.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	16,897.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	532.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	20.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	8.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	20.000
Section 0004 Utilities				
	0590- 70- 5	IRRIGATION SYSTEM- MODIFY EXISTING SYSTEM (45655715201)	LS	1.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (45655715201)	LS	1.000
	1050- 31-202	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 2"	LF	408.000
	1050- 31-204	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 4"	LF	219.000

Call Order: 001 Proposal: E3Y84

ALT	Item	Description	Unit	Quantity
	1080- 21-102	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 2"	EA	1.000
	1080- 24-102	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 2"	EA	3.000
Section 0005 Architectural				
	0750- 1- 19	ARCHITECTURAL, BUILDING, NEW, OTHER BUILDING (45655715201)	LS	1.000
	0750- 1- 19	ARCHITECTURAL, BUILDING, NEW, OTHER BUILDING (45655715201)	LS	1.000
Section 0006 Intelligent Transportation System				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	650.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	598.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	10.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND, 2-12 FIBERS	LF	556.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	6.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	3.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	8.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	975.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0660- 1-104	LOOP DETECTOR, INDUCTIVE, F&I, TYPE 4, 2CHANNEL, SOLID STATE, SHELF MOUNTED, TIME DELAY	EA	4.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0676- 2-806	ITS CABINET, FURNISH & INSTALL, AG STATION ROADSIDE BASE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0685- 1- 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	EA	1.000
	0700-141-060	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I EMBEDDED, BLANK OUT SIGN <12 SF	EA	1.000