

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03260409 Call Order: 005 Proposal: E3Z50-R0 District:03
 Counties: HOLMES, WALTON, WASHINGTON
 Road Name: PONCE DE LEON MAINT - REMOVE AND REPLACE THERMOPLASTIC
 Limits: Midpoint
 Project(s): 42214337240(*) Federal Aid No: N/A
 Total Roadway Length: 0.000 Miles Contract Days: Thru 06/30/27
 Total Bridge Length: 0.000 Miles Letting Date: 04/09/26
 Total Proposal Length: 0.000 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 days
 Proposal Budget Estimate: \$150,000.00

Please read the full advertisement

Description:

The work specified in this Work Document-Driven Contract consists of the removal and replacement of existing reflective pavement markers, thermoplastic stripes and symbols, on a call out basis in Holmes, Walton and a portion of Washington Counties. All work to be performed at night. Mobilization and Maintenance of Traffic are incidental to the pay items listed. This contract has a budgetary estimate of \$150,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder, however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

A Proposal Guaranty will not be required on indefinite quantity contracts, such as work document driven contracts, with a Departments advertised estimate amount of \$150,000 or less regardless of the bid amount.

Call Order: 005 Proposal: E3Z50-R0

ALT	Item	Description	Unit	Quantity
Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	2.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	50.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	500.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	400.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	400.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	50.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	400.000

Call Order: 005 Proposal: E3Z50-R0

ALT	Item	Description	Unit	Quantity
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.000
	0711- 12-101	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6"	GM	1.000
	0711- 12-121	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6" FOR MAINTENANCE USE	LF	400.000
	0711- 12-122	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 8"	LF	400.000
	0711- 12-123	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 12" FOR CROSS WALK OR ROUNDABOUT	LF	400.000
	0711- 12-124	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	400.000
	0711- 12-125	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 24" FOR STOP LINE OR CROSSWALK	LF	400.000
	0711- 12-131	THERMOPLASTIC, REFURBISHMENT, WHITE, SKIP, 6"	GM	2.000
	0711- 12-141	THERMOPLASTIC, REFURBISHMENT, WHITE, 2-4 DOTTED GUIDELINE / 6-10 GAP EXTENSION, 6", MAINTENANCE USE ONLY	GM	2.000
	0711- 12-160	THERMOPLASTIC, REFURBISH, WHITE, MESSAGE	EA	5.000
	0711- 12-170	THERMOPLASTIC, REFURBISH, WHITE, ARROWS	EA	50.000
	0711- 12-201	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	GM	2.000
	0711- 12-221	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6" MAINTENANCE USE ONLY	LF	400.000
	0711- 12-222	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 8" MAINTENANCE USE ONLY	LF	400.000
	0711- 12-224	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON, MAINTENANCE USE ONLY	LF	400.000
	0711- 12-231	THERMOPLASTIC, REFURBISHMENT, YELLOW, SKIP, 6"	GM	2.000
	0711- 12-241	THERMOPLASTIC, REFURBISHMENT, YELLOW 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" MAINT USE ONLY	GM	2.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	2.000
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	2.000
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.000
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	2.000
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	2.000
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.000
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	2.000
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	20,000.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	2.000
	0713-103-141	PERMANENT TAPE, WHITE, 6-10 SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	2.000
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	2.000
	0713-103-281	PERMANENT TAPE, YELLOW, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	2.000

Call Order: 005 Proposal: E3Z50-R0

ALT	Item	Description	Unit	Quantity
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	1,000.000
	E701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	1.000
	E701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	1.000
	E701- 18-221	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SKIP,6"	GM	1.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	1,000.000