

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	03260813	Call Order: 002	Proposal: E3Y73	District:03
Counties:	OKALOOSA			
Road Name:	- FENDER WORK			
Limits:	57030000			
Project(s):	45108635201	Federal Aid No:	N/A	
Project(s):	45108645201(*)	Federal Aid No:	N/A	
Total Roadway Length:	1.226 Miles	Contract Days:	375	
Total Bridge Length:	1.274 Miles	Letting Date:	08/13/26	
Total Proposal Length:	2.500 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Day Flexible	

Proposal Budget Estimate: \$18,844,253.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of FPID 451086-4-52-01 for the Bridge Repair of Spalled Areas, Crack Repairs, Expansion Joints, Cathodic Protection, Bearing Pad Repairs, and Slope Protection and FPID 451086-3-52-01 for replacing the existing fender system "in-kind" with steel HP piles and composite lumber wales for SR 30 (US 98) OVER EAST PASS BRIDGE NOS. 570082 & 570054 in Okaloosa County.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Marine General Liability Insurance as referenced in Section 7-13.5 of the FDOT Standard Specifications may be required if any work under this Contract is performed using vessel(s)*. Prior to the Contract execution, Contractor shall provide written certification to the Department if no vessel(s) will be used for the work.

* Vessel: a watercraft or other artificial contrivance, whether motorized or non-motorized, used to perform some or all of the work, as well as any incidental work related to the project, which includes, but is not limited to, barges, dredges, mobile offshore drilling units, floating cranes, tugboats, ferries, and any watercraft used to transport construction workers, materials, or equipment at the project.

Call Order: 002 Proposal: E3Y73

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	5,819.000
	0110- 1- 1	CLEARING & GRUBBING (45108645201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (45108645201 - Bridge 570054)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (45108645201 - Bridge 570082)	LS	1.000
	0110- 71- 1	BRIDGE FENDER SYSTEM, REMOVAL & DISPOSAL	LF	382.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	117.000
	0400-153-	NON SHRINK GROUT, F&I, MISCELLANEOUS- STRUCTURES REHAB	CF	2.000
	0401- 70- 2	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- STYRENE BUTADIENE	CF	42.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	57.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	30.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	1,444.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	6,725.000
	0450- 82-	BEAM REPAIR	LF	320.000
	0455- 35- 4	STEEL PILING, HP 12 X 53	LF	14,063.000
	0455- 81-102	CATHODIC PROTECTION, F&I, PIER, ZINC ANODE ASSEMBLY	EA	1,485.000

Call Order: 002 Proposal: E3Y73

ALT	Item	Description	Unit	Quantity
	0455- 81-106	CATHODIC PROTECTION, F&I, PIER, OTHER MATERIAL ASSEMBLY	EA	9.000
	0457- 2-131	CATHODIC PROTECTION INTEGRAL PILE JACKET, NON-STRUCTURAL, 30.1" AND LARGER, GALVANIC SYSTEM	LF	490.000
	0457- 2-221	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	209.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	182.000
	0458- 1-101	BRIDGE DECK EXPANSION JOINT, POURED JOINT WITHOUT BACKER ROD	LF	47.000
	0460- 1- 15	STRUCTURAL STEEL - REHABILITATION, MISCELLANEOUS	LB	11,638.000
	0460- 2- 1	STRUCT STEEL, CARBON (45108635201, Bridge ID 570054)	LS	1.000
	0471- 1- 1	FENDER SYSTEM, PLASTIC MARINE LUMBER, REINFORCED	MB	12.300
	0471- 1- 2	FENDER SYSTEM, PLASTIC MARINE LUMBER, NON-REINFORCED	MB	3.200
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (45108635201, Bridge ID 570054)	LS	1.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	2,383.000
	0530- 74-	BEDDING STONE	TN	887.000
	0561- 2-	COATING EXISTING STRUCTURAL STEEL	SF	714.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (45108635201)	LS	1.000
	0101- 1-	MOBILIZATION (45108645201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45108635201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45108645201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	24.000
	0102- 60-	WORK ZONE SIGN	ED	6,688.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	39,056.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	555.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	583.000
	0102-115-	TYPE III BARRICADE	ED	720.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45108635201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45108645201)	LS	1.000
Section 0003 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	10.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.020
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.020
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.020
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.020