Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03261210 Call Order: 001 Proposal: E3Z29 District:03
Counties: ESCAMBIA
Road Name: SR 742 BURGESS RD - RESURFACING
Limits: 48013001
Project(s): 45294715201(*) Federal Aid No: N/A
Project(s): 45294715202 Federal Aid No: N/A

Total Roadway Length:	4.024 Miles	Contract Days:	140
Total Bridge Length:	0.000 Miles	Letting Date:	12/10/26
Total Proposal Length:	4.024 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30 Day Flexible

Proposal Budget Estimate: $2,003,439.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of milling and resurfacing, drainage improvements, curb and gutter, sidewalk, detectable warnings, sod, signalization, signing and pavement markings on State Road 742 (Burgess Road) from SR 95 (US 29) Pensacola Boulevard to SR 742 (Creighton Road), approximately 1.898 miles in Escambia County under 452947-1-52-01. The improvements under 452947-1-52-02 consist of six ECUA manhole adjustments and two ECUA valve box adjustments on State Road 742.

Prequalification is required to bid on this Proposal

Call Order: 001 Proposal: E3Z29

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45294715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45294715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	64.000
	0102- 60-	WORK ZONE SIGN	ED	2,970.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,620.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	280.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	838.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	280.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	280.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	280.000
	0102-115-	TYPE III BARRICADE	ED	8.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	43.000
	0107- 1-	LITTER REMOVAL	AC	98.050
	0107- 2-	MOWING	AC	74.140
	0110- 1- 1	CLEARING & GRUBBING (45294715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	26.000
	0120- 1-	REGULAR EXCAVATION	CY	10.500
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	56.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	21,546.000

ALT	Item	Description	Unit	Quantity
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	8,860.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	13,273.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	1,783.700
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	3,851.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	23.800
	0425- 5-	MANHOLE, ADJUST	EA	6.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	6.000
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0430-963- 1	PVC PIPE FOR BACK OF SIDEWALK, 4"	LF	15.000
	0430-984-160	MITERED END SECTION, NON-STANDARD, OPTIONAL ROUND, 6" SD	EA	2.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	143.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	38.000
	0525- 1-	ASPHALTIC CONCRETE CURB- TO REMAIN	LF	104.000
	0527- 2-	DETECTABLE WARNINGS	SF	78.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	838.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	975.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	3.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,958.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.029
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.016
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,510.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	32.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	987.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.058
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	30.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.262
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	475.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.050
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45294715201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	16.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	11.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	2.000

ALT	Item	Description	Unit	Quantity
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	9.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	838.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45294715201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	367.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	32.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	519.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.058
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	27.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	475.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.050
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	288.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	3.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	3.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	39.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	346.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.022
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.016
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.001
Section 0003 Signalization				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	1.900
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	74.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	140.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	3.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	2.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	2.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	3.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	4.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	2.000

ALT	Item	Description	Unit	Quantity
	0665- 1- 50	PEDESTRIAN DETECTOR, ADJUST/MODIFY ON EXISTING POLE	EA	1.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	3.000
	0670- 5-710	TRAFFIC CONTROLLER ASSEMBLY, MODIFY ONLY - NO COMPONENTS ADDED	AS	2.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000