

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	03260212	Call Order: 001	Proposal: E3Y70	District:03
Counties:	ESCAMBIA			
Road Name:	SR10 FROM PERDIDO RIVER TO W OF BEULAH RD - RESURFACING			
Limits:	48010000			
Project(s):	45293015201(*)	Federal Aid No:	N/A	
Project(s):	45293015202	Federal Aid No:	N/A	
Total Roadway Length:	9.336 Miles	Contract Days:	200	
Total Bridge Length:	0.000 Miles	Letting Date:	02/12/26	
Total Proposal Length:	9.336 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Day Flexible	
Proposal Budget Estimate:	\$3,488,693.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of milling and resurfacing, flexible pavement reconstruction, base work, shoulder treatment, drainage improvements, curb and gutter, ditch pavement, and signing and pavement markings on State Road 10 (US 90A) from Perdido River Bridge to W of Beulah Rd. approximately 3.964 miles in Escambia County under 452930-1-52-01. The improvements under 452930-1-52-02 consist of a valve box adjustment at approximately STA. 2054+67.72 (41.98 LT) on State Road 10.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 001 Proposal: E3Y70

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45293015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45293015201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (45293015201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (45293015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	400.000
	0102- 60-	WORK ZONE SIGN	ED	9,200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	29,800.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	200.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	400.000
	0102-115-	TYPE III BARRICADE	ED	10.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	200.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	60.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	6.000
	0107- 1-	LITTER REMOVAL	AC	586.570
	0107- 2-	MOWING	AC	498.950
	0110- 1- 1	CLEARING & GRUBBING (45293015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	166.000
	0120- 1-	REGULAR EXCAVATION	CY	840.500
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	668.400
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	98.000

Call Order: 001 Proposal: E3Y70

ALT	Item	Description	Unit	Quantity
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	1,796.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	425.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	9,049.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	57,641.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	22,019.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	948.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	1,135.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	683.900
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	9,420.200
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 1-525	INLETS, DITCH BOTTOM, TYPE C, PARTIAL	EA	1.000
	0425- 2- 93	MANHOLES, J-8, PARTIAL	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	120.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	1,382.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	75.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	165.800
	0530- 74-	BEDDING STONE	TN	178.400
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	14,795.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	12.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	2.000
	0695- 6- 11	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 1 LOOP	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,355.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.205
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.096
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	132.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	250.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.800
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.451
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	20.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	57.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	7.126
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.822
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45293015201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	9.624

Call Order: 001 Proposal: E3Y70

ALT	Item	Description	Unit	Quantity
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	12.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	5.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	19.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,355.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45293015201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	132.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	250.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.451
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	7.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	43.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	733.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.091
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	13.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	14.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	8.205
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.096
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.800
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	7.126
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.822
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.292
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.292
Section 0003 Lighting				
	0715- 68-000	LIGHT POLE COMPLETE, RELOCATE	EA	1.000
Section 0004 Signalization				
	0634- 4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	1.000
	0643-600-	STRAIN POLE, WOOD, REMOVE	EA	1.000