

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	03260212	Call Order: 003	Proposal: E3Z31	District:03
Counties:	WALTON			
Road Name:	PONCE DE LEON MAINT - SHLDR REWORK MAINTENANCE			
Limits:	Midpoint			
Project(s):	42214337279(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	THRU 06/30/27	
Total Bridge Length:	0.000 Miles	Letting Date:	02/12/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 DAYS	
Proposal Budget Estimate:	\$450,000.00			

Please read the full advertisement

**Description:**

The Improvements under this Work Document Driven Contract consist of reshaping ditches and reworking shoulders on various roadways in Walton County. These ditches are non-typical and should be re-graded to +/- 3 inches of the original flow line to create a free and unobstructed flow of drainage water. For the purposes of this contract, the original flow line is considered to be the linear projection along the ditch bottom between the invert elevations of immediately adjacent drainage structures. Spoil material removed from ditches and shoulders shall be relocated to FDOT storage pits in Argyle. Mobilization and Maintenance of Traffic are incidental to the pay items listed.

This contract has a budgetary estimate of \$450,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder, however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

**Call Order: 003 Proposal: E3Z31**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 MOTOR GRADER OPERATION (SM)</b>				
	0104- 10- 3	SEDIMENT BARRIER	LF	750.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	50.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	20.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	1,000.000
	E570- 5-	FERTILIZER	TN	2.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	1,000.000
	E573- 1-	HYDRO-SEEDING - APPLICATION OF SLURRY INCLUDING WOOD FIBER, SEED, FERTILIZER, TACKIFIER & DYE	SY	1,000.000
	E575- 1-	SODDING	SY	80,000.000
	E577- 70-	SHOULDER REWORK	SY	80,000.000
	E577- 71-	BLADING PAVED SHOULDER, UP TO 24" BEYOND PAVEMENT	LF	1,500.000