Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03260709 Call Order: 001 Proposal: E3Y94 District:03
Counties: FRANKLIN
Road Name: - BRIDGE-REPAIR/REHABILITATION
Limits: 49010001
Project(s): 42543845201(*) Federal Aid No: N/A

Total Roadway Length:	0.0 Miles	Contract Days:	135
Total Bridge Length:	0.0 Miles	Letting Date:	07/09/26
Total Proposal Length:	0.0 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60 Days Flexible

Proposal Budget Estimate: $2,848,701.00

Please read the full advertisement

Description:

Improvements under this District Contract consist of bridge repair and rehabilitation on SR30 (US 98) over Apalachicola River Bridge No. 490031. Work includes joint replacements, bridge painting, fender repair as well as barrier wall repair, and any additional work to rehabilitate Bridge No. 490031. All work is to be done in Franklin County.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Marine General Liability Insurance as referenced in Section 7-13.5 of the FDOT Standard Specifications may be required if any work under this Contract is performed using vessel(s)*. Prior to the Contract execution, Contractor shall provide written certification to the Department if no vessel(s) will be used for the work.
* Vessel: a watercraft or other artificial contrivance, whether motorized or non-motorized, used to perform some or all of the work, as well as any incidental work related to the project, which includes, but is not limited to, barges, dredges, mobile offshore drilling units, floating cranes, tugboats, ferries, and any watercraft used to transport construction workers, materials, or equipment at the project.

Call Order: 001 Proposal: E3Y94

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	7.000
	0110- 71- 1	BRIDGE FENDER SYSTEM, REMOVAL & DISPOSAL	LF	448.000
	0455- 76-	WRAP PILE CLUSTERS	EA	94.000
	0458- 1- 23	BRIDGE DECK EXPANSION JOINT, REHABILITATION, MODULAR	LF	83.000
	0460- 1- 15	STRUCTURAL STEEL - REHABILITATION, MISCELLANEOUS	LB	2,186.000
	0471- 1- 1	FENDER SYSTEM,PLASTIC MARINE LUMBER,REINFORCED	MB	14.900
	0471- 1- 2	FENDER SYSTEM,PLASTIC MARINE LUMBER, NON-REINFORCED	MB	9.100
	0521- 5- 4	CONCRETE TRAFFIC RAILING- BRIDGE, 32" VERTICAL FACE	LF	24.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (42543845201)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (42543845201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42543845201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,228.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,221.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	298.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,400.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42543845201)	LS	1.000