

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	03260312	Call Order: 002	Proposal: E3Y89	District:03
Counties:	GADSDEN			
Road Name:	SR 63 (US 27) - RESURFACING			
Limits:	50020000			
Project(s):	45080915201(*)	Federal Aid No:	N/A	
Project(s):	45080915202	Federal Aid No:	N/A	
Total Roadway Length:	14.872 Miles	Contract Days:	241	
Total Bridge Length:	0.000 Miles	Letting Date:	03/12/26	
Total Proposal Length:	14.872 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Day Flexible	
Proposal Budget Estimate:	\$5,460,564.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of resurfacing on SR 63 (US 27) from SR 159 to CR 270 Shady Rest Road in Gadsden County. FPID 450809-1-52-01 consist of milling & resurfacing, asphalt widening, shoulder treatment, drainage improvements, curb & gutters, highway signing, guardrail, pavement markings and other incidental construction. FPID 450809-1-52-02 consist of asphalt widening, shoulder treatment, drainage improvements, curb & gutters, highway signing, pavement markings, and other incidental construction to add a southbound left turn lane on SR 63 (US 27) at Rich Bay Road.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 002 Proposal: E3Y89

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45080915201)	LS	1.000
	0101- 1-	MOBILIZATION (45080915202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45080915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45080915202)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	723.900
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	480.000
	0102- 60-	WORK ZONE SIGN	ED	42,657.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	42,046.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	2,410.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	510.000
	0102-115-	TYPE III BARRICADE	ED	5,448.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	482.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	482.000
	0104- 10- 3	SEDIMENT BARRIER	LF	35,027.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	251.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	1,715.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0107- 1-	LITTER REMOVAL	AC	423.590
	0107- 2-	MOWING	AC	383.100

Call Order: 002 Proposal: E3Y89

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (45080915201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45080915202)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,083.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,244.300
	0120- 4-	SUBSOIL EXCAVATION	CY	491.500
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (45080915201)	LS	1.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (45080915202)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	1,887.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,479.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	125,113.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	14,269.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	10,440.400
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	5,020.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,466.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	165.800
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	3.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 82-	REPLACE GRATE	EA	6.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	56.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	400.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	209.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	81.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	3.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	123.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	883.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	3,175.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	7.000
	0536- 73-	GUARDRAIL REMOVAL	LF	2,615.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	11.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	11.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	22,153.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,679.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	7.512
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	401.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	7.443
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.468
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	20.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	6.552

Call Order: 002 Proposal: E3Y89

ALT	Item	Description	Unit	Quantity
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.040
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45080915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45080915202)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	12.796
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	89.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	23.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	19.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	18.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	21.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	44.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,327.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	450.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45080915201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45080915202)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	401.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.216
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	74.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.040
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	7.070
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	7.443
	0711- 15-171	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, 6", 6-10 DOTTED MANAGED LANE MARKING	GM	0.252
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	6.088
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.426
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.464