

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	03260312	Call Order: 005	Proposal: E3Z37	District:03
Counties:	WALTON			
Road Name:	PONCE DE LEON MAINT - RUBBLE PLACEMENT MAINTENANCE			
Limits:	Midpoint			
Project(s):	42214337278(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	Thru 6/30/27	
Total Bridge Length:	0.000 Miles	Letting Date:	03/12/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 DAYS	
Proposal Budget Estimate:	\$250,000.00			

Please read the full advertisement

**Description:**

Improvements under this Work Document-Driven Contract consist of the placement of Bank and Shore Rubble as well as Ditch Lining Rubble along various roadways in Walton County. This rubble will be used to fill, re-contour, and restore eroded slope and ditch bottoms. Periodic lane closures will be required. Removal and replacement of guardrail may be necessary to accomplish dumping and spreading of rubble. All guardrail to be replaced at the end of each workday. Mobilization, Maintenance of Traffic, and removal & replacement of guardrail shall be incidental to the pay items listed.

This Contract has a budgetary estimate of \$250,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder, however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

**Call Order: 005 Proposal: E3Z37**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)</b>				
	0104- 10- 3	SEDIMENT BARRIER	LF	100.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	100.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	10.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,025.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	10.000
	0530- 74-	BEDDING STONE	TN	10.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	50.000
	E575- 1-	SODDING	SY	100.000
	E577- 70-	SHOULDER REWORK	SY	100.000