

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03260514 Call Order: 002 Proposal: E3Z56 District:03
Counties: JACKSON, WASHINGTON
Road Name: MARIANNA MAINT - REMOVE AND REPLACE ALL THERMO AND RPMS
Limits: Midpoint
Project(s): 42212227265(*) Federal Aid No: N/A
Total Roadway Length: 0.000 Miles Contract Days: THRU 12/31/26
Total Bridge Length: 0.000 Miles Letting Date: 05/14/26
Total Proposal Length: 0.000 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 15 DAYS
Proposal Budget Estimate: \$410,000.00

Please read the full advertisement

Description:

The improvements under this Site-Specific Contract consist of the removal and replacement of existing reflective pavement markers and thermoplastic pavement markings on SR 71 South in Jackson County within the concrete roadway surface.

Experience in Pavement Markings Form, No. 850-070-06 is required to be submitted with bid.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 002 Proposal: E3Z56

ALT	Item	Description	Unit	Quantity
Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)				
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	200.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	200.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	3,000.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,200.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	600.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	800.000
	0711- 14-241	THERMOPLASTIC, PREFORMED, YELLOW, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.160
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	43.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	46.000
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.320
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	15,500.000
	0713-103-121	PERMANENT TAPE, WHITE, SOLID W/CONTRAST, 6" PRIMARY LINE WIDTH, FOR CONCRETE SURFACES	GM	1.400
	0713-103-122	PERMANENT TAPE, WHITE, SOLID W/CONTRAST, 8" PRIMARY LINE WIDTH, FOR CONCRETE SURFACES	GM	0.860
	0713-103-123	PERMANENT TAPE, WHITE, SOLID W/CONTRAST, 12" PRIMARY LINE WIDTH, FOR CONCRETE SURFACES	GM	0.120
	0713-103-171	PERMANENT TAPE, WHITE, 3-9 DOTTED, 6" WIDE, FOR CONCRETE SURFACES	GM	0.270
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	1.300
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.100
	0713-103-371	PERMANENT TAPE, BLACK, 3-9 DOTTED, 6" WIDE, FOR CONCRETE SURFACES	GM	1.300
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	5,600.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	750.000