

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	03261113	Call Order: 006	Proposal: E3Z71	District:03
Counties:	LEON			
Road Name:	SR 61 (US 27) MONROE ST @ PARK AVE - TRAFFIC SIGNALS			
Limits:	55040000			
Project(s):	45417015201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.100 Miles	Contract Days:	130	
Total Bridge Length:	0.000 Miles	Letting Date:	11/13/26	
Total Proposal Length:	0.100 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 days flexible	
Proposal Budget Estimate:	\$1,713,705.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of Traffic Signals on SR 61 (US 27) Monroe Street at Park Avenue. Other work includes mast arm replacement, sidewalk replacement, curb and gutter replacement and lighting improvements. All work is to be done in Leon County.

Pre-Qualification is required to bid on this project

Call Order: 006 Proposal: E3Z71

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45417015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45417015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	540.000
	0102- 60-	WORK ZONE SIGN	ED	4,340.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,506.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	14,400.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	25.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	548.000
	0102-115-	TYPE III BARRICADE	ED	112.000
	0104- 10- 3	SEDIMENT BARRIER	LF	119.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	3.000
	0107- 1-	LITTER REMOVAL	AC	0.150
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (45417015201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (45417015201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.010
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	146.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	67.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	148.000
	0526- 1-101	PAVERS, ARCHITECTURAL, REMOVE EXISTING AND REINSTALL	SY	16.000
	0527- 2-	DETECTABLE WARNINGS	SF	65.000

Call Order: 006 Proposal: E3Z71

ALT	Item	Description	Unit	Quantity
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	47.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45417015201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	174.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,510.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	4.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	10.000
	0715-511-120	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 20'	EA	5.000
Section 0003 Signalization				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.100
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	226.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	546.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	130.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	21.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	4.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	12.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	1.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	1.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	130.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	44.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	20.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	12.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	4.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 21- 7	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 50'-30'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0649- 21- 24	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 78'-50'	EA	1.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	4.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	10.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	2.000

Call Order: 006 Proposal: E3Z71

ALT	Item	Description	Unit	Quantity
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	12.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	2.000
	0663- 1-112	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, DETECTOR	EA	4.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	1.000
	0663- 1-123	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, CABINET ELECTRONICS	EA	1.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	12.000
	0670- 5-182	TRAFFIC CONTROLLER ASSEMBLY, F&I, CALTRANS W/STANDARD LOCK, 2 PREEMPTION	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0682- 1-173	ITS CCTV CAMERA, NON-PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	1.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	5.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	6.000
	0700-141-330	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I OVERHEAD MOUNT, ELECTRONIC DISPLAY SIGN	EA	2.000