

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	03261008	Call Order: 002	Proposal: E3Z44	District:03
Counties:	HOLMES			
Road Name:	SR79 AG PULLOFF INSPECTION SITE - MISC CONSTRUCTION			
Limits:	52030000			
Project(s):	45657325201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.152 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	10/08/26	
Total Proposal Length:	0.152 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Day Flexible	
Proposal Budget Estimate:	\$905,173.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of the construction of a new SR 79 Agricultural Pulloff Inspection Site in Holmes County. The proposed work is to include the addition of pavement, lighting systems, ITS systems, signing, and pavement markings, along with associated earthwork.

Call Order: 002 Proposal: E3Z44

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45657325201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45657325201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,560.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,120.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	268.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	120.000
	0104- 10- 3	SEDIMENT BARRIER	LF	870.000
	0107- 1-	LITTER REMOVAL	AC	5.030
	0107- 2-	MOWING	AC	5.030
	0110- 1- 1	CLEARING & GRUBBING (45657325201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	402.600
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	2,081.600
	0160- 4-	TYPE B STABILIZATION	SY	2,553.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	2,314.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	251.200
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	188.400
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	362.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	3.000
	0570- 1- 1	PERFORMANCE TURF	SY	1,984.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45657325201)	LS	1.000

Call Order: 002 Proposal: E3Z44

ALT	Item	Description	Unit	Quantity
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	2.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	2.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	3.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	140.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	12.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.055
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.396
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	740.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	8.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	53.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,319.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	5.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	5.000
Section 0004 Intelligent Transportation System				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,449.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	1,377.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	2.000
	0676- 2-811	ITS CABINET, FURNISH & INSTALL, AG PULL-OFF ROADSIDE BASE MOUNT WITH SUNSHIELD, 336, 24" W X 36" H X 20" D	EA	1.000
	0676- 3- 11	SMALL EQUIPMENT ENCLOSURE, FURNISH AND INSTALL, GREATER THAN 10"W X 13"H X 11" D	EA	2.000
	0700-141-060	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I EMBEDDED, BLANK OUT SIGN <12 SF	EA	1.000